

G

Company: Eagle-Picher

Sec. 6 T. 34 R. 24

Farm: O. A. Rhodes No. 3

Loc. 100'S of C SE SW

Comm. March 6, 1942

County: Cherokee

Comp. March 18, 1942

Total Depth: 425

Contractor: W. J. Swalley

Water Level: 15

Driller: Lloyd George

Elevation: 887

Formation

	Thickness	Depth
soil	1	1
clay, yellow	11	12
soapstone, gray	23	35
soapstone, dark gray	115	150
sandstone, brown	5	155
lime, tan; flint, light gray	20	175
lime, gray and tan	15	190
lime, gray; flint, light gray	10	200
lime, gray and light gray sandy	10	210
flint, gray and brown speckled; specks of gray lime	5	215
lime, gray; flint, light gray	15	230
lime, gray; flint, gray and blue	15	245
flint, gray; cotton rock	25	270
lime, gray; flint, light gray	30	300
lime, gray and tan; flint, gray	15	315
specks of gray lime; flint, light gray	5	320
lime, gray and tan	20	340
lime, gray and tan; flint, gray	15	355
lime, gray; flint, light gray	5	360
cotton rock; flint, light gray	15	375
flint, gray; specks of gray lime	5	380
flint, gray	20	400
lime, gray and brown; flint, light and dark gray	10	410
lime, dark gray; flint, gray and light blue spotted	5	415
specks of gray lime; flint, gray and blue	5	420
lime, gray flakey; flint, blue	5	425

Water at 40 ft.

Water at 60 ft. and 150 ft.

Set 175 ft. of 6 $\frac{1}{4}$ casing