

G

Company: Eagle-Picher

Sec. 15 T. 34 R. 25

Farm: Swan-Glick

No. P-4A

Loc. 375'S, 110'E of C of
NW SE

Comm. March 12, 1942

County: Cherokee

Comp. April 1, 1942

Total Depth: 216

Contractor: S. F. Bradbury

Water Level: 20

Driller: H. E. Rentfrow & Ira Senior
R. A. Palmer, Helper

Elevation: 876

	Formation	
	Thickness	Depth
soil and yellow clay	20	20
flint, yellow blue and gray; shelly formation	25	45
flint, blue and gray; good showing of zinc; few lead shines; shelly formation	5	50
flint, blue and gray, showing few zinc shines, shelly formation	5	55
flint, blue; and gray; fair showing of zinc, shelly formation	10	65
flint, blue and gray; showing few zinc shines, shelly formation	20	85
flint, blue and gray, showing good zinc shines, shelly formation	5	90
flint, blue and gray, fair showing of zinc, shelly formation	5	95
flint, blue and gray; good showing of zinc, shelly formation	5	100
flint, blue gray and black; good showing of zinc; open selvage formation	13	113
flint, blue gray and white; fair showing of zinc and trace of lead; hard formation	12	125
flint, blue gray and white, showing good zinc shines and trace of lead; hard formation	5	130
flint, gray and white, showing few zinc shines, and trace of lead; hard formation	15	145
flint, gray and white, showing trace of zinc; hard formation	15	160
flint, white, blue and brown; hard formation	15	175
lime, gray; flint, blue; hard formation	41	216

ASSAY:

		Blende			Blende
45	50	6.15	115	120	2.50
50	55	0.25	120	125	0.90
95	100	1.20	125	130	1.30
100	105	1.25	135	140	0.65
			110	113	2.10