

G

Company: Eagle-Picher

Sec. 15 T. 34 R. 25

Farm: Swan-Glick

No. P-10

Loc. SE NW SE--185' SE of P-6

Comm. April 28, 1942

County: Cherokee

Comp. May 9, 1942

Total Depth: 230

Contractor: H. S. Thomas

Water Level: 20

Driller:

Elevation: 874

Formation

	Thickness	Depth
soil and clay	25	25
lime, gray; flint, white and blue	12	37
flint, blue; good lead shines	10	47
flint, blue; fair lead shines	7	54
flint, loose gray; thin lead shines	3	57
flint, loose blue; thin lead shines	43	100
flint, loose blue and gray	15	115
flint, hard light gray	25	140
flint, hard light gray; thin jack shines	25	165
flint, dark gray; thin jack shines	25	190
flint, dark blue; lime, brown	40	230

ASSAY:

		Blende	Galena
145	150	0.95	
150	155	1.60	
155	160	1.40	
160	165	0.85	
165	170	0.95	
170	175	0.55	
175	179	0.35	
179	185	0.40	
185	190	0.30	
37	47	0.10	7.07
47	51		0.23

65 ft. of 8 1/2 pipe

115 ft. of 6 1/2 pipe