

G

Company: Eagle-Picher No. 7
 Farm: Kansas-Mo. Land & Mining Co.
 Comm. August 13, 1942
 Comp. August 17, 1942
 Contractor: Denton Bros.
 Drillers: Claude Denton (day)
 Jim Sheperd (night)

Sec. 22 T. 34 R. 25
 Loc. SE NE NE; 150 NE
 of #5
 County: Cherokee
 Total Depth: 200
 Water Level: 50
 Elevation: 910

Formation		
	Thickness	Depth
surface; clay, yellow; flint, gray and light gray; coarse formation	5	5
flint, gray and light gray; clay, yellow; coarse formation	5	10
flint, gray, light gray and pink; coarse formation	30	40
flint, gray, light gray and pink; " "	25	65
flint, gray and light gray; coarse formation	10	75
flint, glassy light gray and gray; solid formation	15	90
flint, glassy light gray and gray; thin jack traces	5	95
lost cuttings; bouldery ground	5	100
flint, gray and light gray; thin jack traces	5	105
flint, light gray and white; thin jack traces	5	110
flint, light gray, white and pale blue	5	115
flint, light gray, white and pale blue	5	120
lime, brown; flint, dark blue and light gray; thin jack traces	5	125
lime, brown; flint, dark blue and light gray; thin jack traces	5	130
lime, brown and gray; flint, dark blue and gray	20	150
lime, brown and gray; flint, dark blue	10	160
lime, gray and green; flint, gray and dark blue	5	165
lime, gray and light gray; flint, gray and dark blue; selvage, light gray	5	170
lime, gray and green; flint, gray and light gray; selvage, light gray	5	175
flint, gray and light gray; lime, green; selvage, light gray and green	5	180
cotton rock, light gray; lime, gray; flint, gray and light gray	5	185
cotton rock, light gray; lime, gray; flint, gray and light gray	5	190
cotton rock, light gray; lime, gray; flint, gray and light gray	5	195
cotton rock, light gray; lime, gray; flint, gray and light gray	5	200

Struck water at 55 ft.

74' of 6 $\frac{1}{4}$ pipe.