


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JOHN LINDAS OIL COMPANY
 Farm- Shurtz No. 1

SEC. 29 T. 34 R. 3E
 SE SW NE

Total Depth. 3438
 Comm. 8-19-52 Comp. 8-31-52
 Shot or Treated.
 Contractor. Capitt Drilling, Inc.
 Issued. 11-8-52

County Cowley KANSAS



CASING:
 8 5/8" 94'
 5 1/2 3436'

Elevation. 1133 D.E.
 1135 (sand)
 Production. Physical potential
 25 BOPD

✓
 Figures Indicate Bottom of Formations.

shale	70
lime	210
red rock	380
lime, shale	480
red rock	495
shale, lime	920
shale, shells	1095
shale, lime	1355
lime	1411
shale, sand	1445
shale sandy	1458
shale, shells	1520
lime, shale	1765
lime	1847
lime, shale	1870
shale, lime, red rock	1940
sand	1955
shale, lime	2150
shale, redrock, sand	2265
shale, lime shells	2300
sand	2335
sand, lime	2367
sand	2387
shale, lime, sand	2465
shale, shells	2646
sand	2800
shale sandy	2857
lime	2965
lime, shale	2985
sand, shale sdy	3060
shale, lime	3325
shale	3373
sand	3392
lime Miss.	3438
Total Depth	

Tops: Drillers
 Layton 2646
 Bartlesville Sand 3364
 Miss. Lime 3392

Core Record: Diamond
 Core Head -6" 3355-3392
 Perforate 132/3375-89
 Hydrafrac
 Physical Potential 25 bopd