


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

SINCLAIR PRAIRIE OIL CO.
E. W. Shurtz No. 1.

SEC.29 T.34 R.3E
SW NW NE
330'f SL 330'f WL NW $\frac{1}{4}$ NE $\frac{1}{4}$

Total Depth. 3391'
Comm. 6-22-41 Comp. 7-20-41
Shot or Treated. 40 Qts. 7-21-41 3373-90
Contractor. Harbar Drlg.Co.
Issued. 10-25-41

County. Cowley



Rotary O-3337
Cable 3337-91

CASING:

10 $\frac{3}{4}$ " 113' LI
7" 2658' LI
5 $\frac{1}{2}$ " 90' liner LI
2" 3387' LI

Elevation.

Production. Pot.389 B.

Figures Indicate Bottom of Formations.

surface clay	45	Top Bartlesville 3354
sand	60	
clay & shells	135	90' of 5 $\frac{1}{2}$ " OD liner
lime & shale	510	perforated and set
lime	565	on btm
shale & lime shells	625	
red bed	740	
shale & shells	1435	
lime & shale	1685	
shale & red bed	1745	
shale & shells	1770	
lime	1825	
lime & shale	1970	
shale	1985	
sdv lime	2020	
lime & shale	2195	
shale & lime(cored)	2211	
shale	2229	
lime & sand	2241	
sand	2268	
sdv shale	2335	
lime	2345	
sand	2353	
shale	2370	
sdv lime	2410	
lime & shale	2535	
shale & lime shells	2585	
shale(cored 2652-70)	2670	
sand & lime	2706	
(cored 2688-2706)		
sdv shale	2765	
shale	2800	
shale & lime	2872	
lime (cored 2879-90)	3005	
shale(cored 2890-2901)	3025	
sand & sdv shale	3050	
(cored 2901-08)		
lime & shale	3130	
lime	3165	
lime & shale	3328	
(cored 3328-46)		
sdv shale	3346	
shale dk	3354	
sand (sh oil 3367)	3370	
shale	3373	
sand Bartlesville	3390	
shale	3391	
Total Depth.		

1st 24 hrs natural no production
1st 24 hrs after shot 65 B.
7-26-41 Pot. test 7" csg 315 Bbls.
8-11-41 Pot. test 2" tbg 389 Bbls.

Core Record: 2195-2211, 2652-70
2688-2706, 2879-2908,
and 3328-46