


SINCLAIR PRAIRIE OIL CO.
E.W. Shurtz No. 3.

SEC. 29 T. 34 R. 3 E
NW SW NE
990' f SL 330' f WL NE $\frac{1}{4}$

Total Depth. 3380'
Comm. 9-23-42 Comp. 11-4-42
Shot or Treated. 30 Qts. 10-26-42 3365-80
Contractor. Harbar Drlg. Co.
Issued. 12-26-42

County. Cowley



CASING:
10 $\frac{3}{4}$ " 82' Cem. LI
5 $\frac{1}{2}$ " 3341' Cem. LI

Elevation.

Production. Pot. 73.08 B.

Figures Indicate Bottom of Formations.

surface clay	10	60' of 4" special liner
shale & shells	55	ran in well - made of
sand	60	4" line pipe with
shale & lime	82	special inserted
shale & shells	345	threads-set on btm,
shale & lime	490	perforated from btm
lime	525	up to 15'
shale & shells	685	
red bed & shale	715	
shale & shells	1418	
shale	1425	
lime	1733	
shale & lime	1833	
shale	1990	
shale & lime	2048	
shale & lime shells	2105	
shale	2210	
shale & lime	2260	
sand	2360	
shale & shells	2405	
shale	2675	
sand	2685	
lime sdy	2770	
shale & shells	2810	
shale	2860	
shale & lime	2925	
lime	2995	
shale	3020	
lime sdy	3035	
shale	3070	
lime	3085	
shale & lime	3115	
lime	3170	
shale & sand	3220	
shale & lime	3265	
shale	3333	
cooring (shale)	3339	
shale & lime	3348	
shale & sdy shale	3355	
sand	3380	
Total Depth.		

1st 24 hrs after shot 52 B.
2nd 24 hrs after shot 35 B.
Pmp Pot. 73.08 B.

Cored 3320-51 two cores

Bartlesville 3355-80
Producing from Bartlesville
sand; first oil at 3364