

**WELL COMPLETION REPORT AND DRILLER'S LOG**

API No. 15 — 035 — 22240 ✓  
County Number

Operator JENKINS AND BROYLES PROD. CO.

Address ROUTE 2 BOX 20 ARKANSAS CITY, KANSAS 67005

Well No. 1 Lease Name MARRS

Footage Location  
660 feet from (N) ~~to~~ line 660 feet from (E) (W) line

Principal Contractor COMPANY TOOLS Geologist COMPANY

Spud Date 8-24-79 Date Completed 9-2-79 Total Depth 802' P.B.T.D.


Directional Deviation Oil and/or Gas Purchaser CARFIELD GAS GATHERING SYSTEMS

S. 31 T. 34S R. 3 E

Loc. NW-SE

County COWLEY

640 Acres  
N



Locate well correctly

Elev.: Gr. 1175

DF \_\_\_\_\_ KB \_\_\_\_\_

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	7-7/8	5 1/2	15 1/2	193'	PORTLAND	100	NONE
PRODUCTION	4-3/4	2-7/8	6.70	801'	PORTLAND	100	NONE

**LINER RECORD**

Top, ft.	Bottom, ft.	Sacks cement

**PERFORATION RECORD**

Shots per ft.	Size & type	Depth interval
2	2" JET	745-749'

**TUBING RECORD**

Size	Setting depth	Packer set at
NONE		

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
500 GALLONS 15% ACID	745-749'

**INITIAL PRODUCTION**

Date of first production <u>SHUT IN</u>	Producing method (flowing, pumping, gas lift, etc.) <u>FLOW</u>				
RATE OF PRODUCTION PER 24 HOURS	Oil <u>NONE</u> bbls.	Gas <u>150</u> MCF	Water <u>NONE</u> bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold) <u>WILL SELL WHEN COMPRESSOR IS SET</u>			Producing interval (s) <u>745-749'</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

JENKINS AND BROYLES PROD. CO.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDOW, ETC.:

Well No.

1

Lease Name

MARRS

GAS

S 31 T 34S R 3 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SOIL AND CLAY	-0-	45'		
SHALE AND LIME	45'	275'		
LIME AND SHALE	275'	660'		
RED SHALE	660'	740'		
NEVA LIME	740'	802'		
TOTAL DEPTH		802'		
			GAMMA RAY NEUTRON LOG	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Edward L. Broyles*  
 EDWARD L. BROYLES Signature  
 GENERAL PARTNER  
Title  
 4-5-80  
Date