


SINCLAIR PRAIRIE OIL CO.
Lola Robertson No. 1

SEC. 20 T. 34 R. 3 E
SE SW SE
330' FEL330' FSL SW $\frac{1}{2}$ SE $\frac{1}{2}$

Total Depth. 3388
Comm. 12-16-41 Comp. 1-22-42
Shot or Treated.
Contractor. Harbar Drlg Co.
Issued. 3-14-42

County Cowley.



CASING.

103/4" 119' cement

Elevation.

7" of 5" liner set on bottom of hole 3388
Perforated up to 60'
Figures Indicate Bottom of Formations.

Production. Pot. 184.44B.

cellar	10	1st 24 hours after shot	67 bbls.
shale and shells	123	2nd 24 hours after shot	43 bbls.
lime	140		
shale and shells	240	Pot. test 2-11-42	184.44 bbls.
sdv lime	345		
shale and lime shells	475	Core No. 1	3325-3343
red rock	485		
lime	535	Bartlesville	3357-3386
shale and shells	595	Chat	3386-3388
red bed	660		
shale and shells	695	40 qts	3360-3388 1-12-42
shale	735	80 qts	3362-3388 1-16-42
sand	750		
shale lime shells	900		
shale and shells	1335		
sand and shale	1355		
shale and shells	1410		
shale	1530		
shale and shells	1550		
lime	1605		
lime and shale	1685		
lime shells & shale	1730		
shale	1800		
lime	1850		
shale	1860		
shale and lime	1965		
lime	2000		
shale and shells	2140		
shale	2235		
sand	2340		
sdv lime	2350		
shale and shells	2335		
shale	2450		
shale and shells	2510		
shale	2635		
shale and shells	2672		
sand	2695		
sdv lime	2810		
shale	2875		
sdv shale	2890		
shale	2900		
lime	2990		
sand	3010		
shale	3070		
lime	3085		
lime hard	3120		
lime and shale	3155		
lime	3175		
shale	3205		
lime	3220		
shale and shells	3245		
shale	3270		
sdv lime & shale	3280		
shale	3295		
shale and Br. lime	3300		
shale	3357		
sand	3386		
chat	3388		
Total Depth.			