

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

14-34-3E


Company- CHESTER WILLIAMS et al
Farm- Community No. 1

SEC. 14 T. 34 R. 3E
CW/2 SW SW NW

100' E of WL, 330' N of SL, SW $\frac{1}{4}$
NW $\frac{1}{4}$
County Cowley

KANSAS

Total Depth. 3406 RB
Comm. 1-12-53 Comp. 1-25-53
Shot or Treated.
Contractor. Crest Drilling Co.
Issued. 2-14-53



8 5/8" CASING:
96' cem w/80 sx

Elevation. 1167

1169(2nd)

Production. dry

Figures indicate Bottom of Formations.

sand	50
shale blue	85
lime	90
lime hard	96
shale, lime	1270
shale sandy	1390
shale, lime	2195
sand	2325
lime sandy, shale	2380
shale sandy	2470
shale, sand	2540
shale	2615
sand (Layton)	2780
shale	2835
lime Kansas City	2895
lime	2950
shale sandy, shale	3023
lime, shale	3215
shale	3339
cored	3375
shale	3387
conglomerate	3398
mississippian	3406RB
Total Depth	

Tops: Scout.	
Layton	2656
Kansas City	2837
Bartlesville Zone	3323
Bartlesville Sand	3357
Conglomerate	3385
Miss. lime	3398

All measurements from rotary
bushing 2 $\frac{1}{2}$ feet above derrick
floor.