

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 12/14/82
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API NUMBER Drilling Completed 12/7/70 (of this well) ^{6/87}
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Stelbar Oil Corporation, Inc. OPERATORS LICENSE NO. 6044

ADDRESS 155 North Market, Suite 500 PHONE # (316) 264-8378
Wichita, Kansas 67202

LEASE (FARM NAME) Jones Unit (McLaughlin #6) WELL NO. I-1

WELL LOCATION C S $\frac{1}{2}$ SW $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$ SEC. 30 TWP. 34S RGE. 3 (E) ~~XX~~

COUNTY Cowley TOTAL DEPTH 3415 FIELD NAME Murphy

check one:

OIL WELL GAS WELL INPUT WELL SWD WELL D&A

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not, explain) Old Well

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Martin B. Shawver ADDRESS Box 119, Douglass, KS 67039

PHONE # (316) 782-3215

PLUGGING CONTRACTOR Chet Shephard Drilling Co. LICENSE NO. 6046 ^{6/87}

ADDRESS Box 9, Geuda Springs, KS 67051 PHONE # (316) 447-3377

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Stelbar Oil Corporation, Inc.

ADDRESS 155 North Market, Suite 500 PHONE # (316) 264-8378
Wichita, Kansas 67202

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OR ACTING AGENT.

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1986

SIGNED: Martin B. Shawver
(Applicant or Acting Agent)

Martin B. Shawver, Production Supt.
DATE: July 11, 1986

CONSERVATION DIVISION
Wichita, Kansas

2



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

OCT 15 1986
EXPIRES

July 15, 1986

WELL PLUGGING NOTICE

Jones Unit (McLaughlin #6)I-1
C S/2 SW/4 NW/4 NE/4
Sec. 30-34S-3E
Cowley County

Stelbar Oil Corporation, Inc.
155 North Market, Ste. 500
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please contact the district office to review your suggested method of plugging
DIST. #2 3244 E. Douglas Wichita, KS 67208 316-651-5506
five days prior to plugging the well (KAR-82-3-113).

2 060432

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- drill 1970

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Operator: Stelbar Oil Corp.
Name & Address: 155 N. Market, Suite 500
Wichita, KS

C S/2 SW NW NE SEC. 30, T 34 S, R 3 W/E
_____ feet from S section line
_____ feet from E section line

Lease Name Jones Unit McLaughlin #6 Well # 1

County Cowley 110.99

Well Total Depth 3415 feet

~~XXXXXXXX~~ Pipe: Size 5 1/2 feet 3395

Surface Casing: Size 8 5/8 feet 177

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____ open hole

Plugging Contractor Shephard Drilling License Number _____

Address Geuda Springs, KS

Company to plug at: Hour: _____ Day: 16 Month: 9 Year: 19 86

Plugging proposal received from _____

(company name) _____ (phone) _____

were: sand bottom to 3375' and dump 6 sacks of cement - rip and pull 5 1/2" -
bridge plug 375-350 feet - bail dry - redi mix to surface.

Plugging Proposal Received by _____ District office
(TECHNICIAN)

Plugging Operations attended by Agent?: All top Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 16 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT Pushed plug to 3380 feet and 5 feet rock, dumped 6 sacks of
cement. Ripped 2000 feet of 5 1/2" casing. Built bridge plug 375-340 feet.

Haynes Concrete dumped 5 1/2 yards of
redi-mix to surface. Siphoned water to pit. Pulled 2" and backe filled hole.

Remarks: #8266
(If additional description is necessary, use BACK of this form)

INVOICED

DATE 9-19-86

Signed [Signature]
(TECHNICIAN)

INV. NO. 14980

NOV 14 1986

DRILLER'S LOG

COMPANY: Crest Petroleum, Inc.
CONTRACTOR: Wrico Drilling, Inc.
FARM: McLaughlin No. 6
LOCATION: C S/2 SW NW NE, Sec. 30-34-3E
Cowley County, Kansas

COMMENCED: November 29, 1970
COMPLETED: December 7, 1970
(rotary)

Elevation: 1163 K.B. (1155 Gr.)

Surface Casing: 8-5/8" @ 177' W/100 sks
5 1/2" @ 3395' W/150 sks

<u>FORMATION</u>	<u>DEPTH</u>
Shale, lime	300
Shale, redbed, lime streaks	570
Shale, redbed	800
Shale	1175
Shale, sand	1400
Shale, lime	1800
Shale, sand	1980
Shale, lime	2188
Shale	2228
Lime	2238
Sand, shale	2530
Shale	2698
Sand, shale	2836
Shale, sand	2882
Lime	3003
Shale	3023
Sand, shale	3105
Lime, shale	3272
Shale	3385
Rotary Total Depth	3412 1/2

<u>TOPS</u>	
Iatan Lime	2228
Stalnaker Sand	2262
Hogshooter Lime	2661
Layton Sdy Zone	2681
Layton Sand	2703
Kansas City Lime	2882
Cleveland Sand	3021
Marmaton Lime	3091
Cherokee Shale	3209
Cattleman Sdy Zone	3296
Bartlesville Sand	3380

2703
1163
1540

3021
1163
-1858

I hereby certify that this is a true and correct record and log of the well drilled on the above-mentioned location to the best of my knowledge and belief.

WRICO DRILLING, INC.

W. W. Wright
W. W. Wright

STATE OF KANSAS SS
COUNTY OF SEDGWICK

Subscribed and sworn to before me this 19th day of August, 1974 as a Notary Public, within and for said County and State above.

Patra M. Wilshire
Patra M. Wilshire-Notary Public



RECEIVED

Conservation Division, Kansas March 13, 1976

JUL 15 1986

CONSERVATION DIVISION
Wichita, Kansas

