


Plot
11

W. M. MCKNAB
Henry Waldschmidt No. 1.

SEC. 18 T. 34 R. 6E
SWc NW

Total Depth. 3520'
Comm. 12-22-36 Comp. 3-29-37
Shot or Treated.
Contractor. McKnab Drlg. Co.
Issued. 5-22-37

County. Cowloy



CASING:
15 1/8" 348'
13 3/8" 1342'
10 1606'
8 1/4" 2487'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	8	lime white	1120	lime white	2045
red rock	23	lime brown	1130	sand drk	2048
lime	30	shale blk	1135	shale drk	2055
shale	35	lime white	1140	sdv lime	2065
lime	55	shale blue	1145	shale blue	2085
red rock	85	lime white	1150	shale blk	2140
shale	90	shale blue	1155	shale blue	2150
lime	105	lime white	1175	shale drk	2208
shale blue	117	shale drk	1185	lime sdv	2224
red rock	122	lime brown	1205	shale grey	2230
shale	130	shale blue-HFW 1235-	1225	sand white	2260
lime	150	sand grey- hole cavg -1248		HFW 2230-45	
red rock	175	shale blue-SLM 1256-	1260	shale blue-Hole cavg-2270	
shale blue	200	shale blue-hole cavg -1265		sand grey	2280
red rock	220	lime white	1272	shale blue	2287
shale white	225	sand white	1306	sand white (water)	2309
red rock	245	shale blue	1313	coal	2310
lime white	300	sand white	1332	sand white	2350
shale white	310	Corr. SLM 1337		sand grey	2355
4 BW 330-35		lime grey	1342	shale blue	2385
lime white	343	shale blue	1432	sdv lime	2390
SIM 348'		lime grey	1437	shale blue	2400
lime white	379	shale blue	1458	sand white	2435
shale blue	390	lime white	1465	shale blue	2442
lime white	400	shale white	1475	lime	2455
shale blue	405	red rock	1480	shale blue	2460
lime white	430	shale white	1500	lime blk	2468
shale white	465	lime white	1525	lime grey	2475
lime white	470	shale white	1540	shale lgt	2478
shale lgt	485	shale pink	1555	shale drk	2523
shale drk	510	lime grey	1560	lime	2540
sdv shale	520	shale blue	1578	sdv shale	2605
shale drk	525	sand	1606	shale lgt	2625
lime white	530	Gas 1580-81 5,212,000		lime white	2655
shale white	550	Reduced hole 1581, Wtr 1587-1589		lime brown	2668
lime white	555	5 days shutting off gas		shale drk	2685
shale blue	630	shale blue	1657	lime brown	2695
lime white	640	sand drk	1667	lime grey	2705
shale lgt	695	shale blue	1745	lime Sh oil 2710	2710
shale blue	716	lime white	1755	shale blk	2723
lime grey	740	shale blue	1765	lime white	2745
lime white	750	lime white	1772	lime brown	2750
shale blue	765	sdv lime	1782	shale drk	2755
lime white	770	sand white	1792	lime brown	2760
lime shells & shale	785	shale blue	1810	shale blue	2890
lime white	790	lime brown	1813	shale pink	2895
lime brown	815	shale blue	1830	shale lgt	2927
shale blue	820	lime white	1833	red rock	2932
sdv shale	830	shale blue	1848	Corr. 2938 SIM	
shale blue	875	lime white	1860	red rock	2945
lime white	905	shale blue	1965	Reduced hole 2938	
shale blue	925	sand white	1985	sdv shale	2949
lime white	940	Drilling HFW, Pipe did not		sand Sh oil 2952	2952
shale drk	945	shut off		red rock	2960
lime white	960	shale lgt	1990	sand white	2967
shale blue	1000	sdv lime	2005	slate black	2980
lime shells & shale	1020	sand white	2016	shale drk	3010
shale blue	1030	shale drk	2018	shale blue	3032
red rock	1035	shale blue	2021		
shale blue	1045	lime hrd	2029	(OVER)	
lime brown	1100	sand white	2040		

ohat 3032-44

Washed oil 3042-47

lime 3047

lime white 3053

Washed oil 3049-51

lime grey 3082

lime drk 3103

lime lgt 3106

lime sdy 3120

little wtr 3106-20

lime white 3125

lime grey 3140

lime white 3175

lime grey 3180

sand 3185

sdv lime 3211

lime white 3234

lime grey 3309

Carrying 2 section BWPB

60' tube 3378

lime black 3440

shale green 3446

lime white 3449

shale blk 3510

Wilcox sand 3520

Hole filling up with wtr

3515-20

Total Depth.

WATER RECORD

4 BW 330-335

12 BW 1225

HFW 1235

Water 1587-89

HFW 2230-45

Little water 3106-3120

HFW 3515-20