

**F. W. MORGAN**  
GEOLOGIST

P.O. BOX 18602  
WICHITA, KANSAS 67218

Aug 11, 1982

WICHITA OFFICE 685-6361  
COYVILLE OFFICE 692-5473

Watson Petroleum, Inc.  
302 Hillcrest  
Wichita, Kansas

Re: No. 2 Kubik  
Sec. 28-34S-6E  
Cowley County, Kansas

Gentlemen:

Enclosed is my geological log on the No. 2 Kubik. On the log is all geological data gained from the drilling of this well. Generally the well ran 10 feet higher than No. 1 Kubik on reliable geological markers. Following are shows of oil found:

Layton Sand - 2722 - 25' - A very poor show of heavy oil with dull fluorescence and no odor. Not considered to be commercial.

Pawnee - 2770 - 78' - porosity poorer than in No. 1. Zone was thinner, too. Consequence is poorer show. This zone is an unknown in the area but is believed to be of very questionable value.

Mississippian - 3111 - 3117' - Fair pinpoint porosity, good show of free oil, odor, fluorescence.  
3122 - 3127' - poor porosity, light oil, possible prospect.

Casing was run to test the Mississippian, especially the top zone.

Sincerely,

  
F. W. Morgan