


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **ROCK ISLAND OIL & REFINING CO.**
Farm- **Austin** No. **1**

SEC. **2** T. **35** R. **1E**
C SW NW

Total Depth. **3895'**
Comm. **4-9-64** Comp. **4-21-64**
Shot or Treated.
Contractor. **White & Ellis**
Issued. **6-13-64**

County **Sumner**
KANSAS



CASING:

8 5/8" 249' cem w/ 200 sx

Elevation. **1146' KB**

Production. **DRY**

Figures Indicate Bottom of Formations.

soil	20
shale	80
shale & lime	100
anhydrite	140
shale & shells	200
lime & shale (strks)	250
lime & shale	460
lime & shale (Strks)	845
red rock	905
lime w/shale strks	1420
shale & lime	1735
lime	2180
shale & lime	2416
lime	2423
sandy shale	2480
sand	2659
lime & shale	2778
shale	2850
lime	2868
shale	2898
sand	3034
shale	3090
lime	3170
shale	3187
sand	3262
lime	3420
shale-lime	3435
shale	3532
lime	3704
shale	3718
shale & lime	3760
Dolomite & shale	3778
sand	3808
shale	3878
lime	3895
Total Depth	

TOPS: LOG	
Anhydrite	140
Brown lime	2416
Stalnaker	2480
Layton	2898
Kansas City	3090
Cleveland	3187
Marmathon	3262
Cherokee	3391
Cherokee sand	3452
Mississippi	3532
Kinderhook	3704
Chattanooga	3760
Simpson	3778
Arbuckle	3878