


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HERNDON DRILG. CO.
Farm- Gurley No. 2

SEC. 6 T. 35 R. 1E
NW SW NE

Total Depth. 3860
Comm. 7-21-51 Comp. 8-7-51
Shot or Treated.
Contractor.
Issued. 9-29-51

County Sumner
KANSAS



CASING:

8 5/8" 428' cem. w/250 sx
5 1/2" 3854' cem. w/250 sx

Elevation 1099
1102 RE
Production. Pot. 2039

Figures Indicate Bottom of Formations.

shale & sand	70
shale & shells	355
shale & lime	428
shale & shells	575
shale & lime	750
sand	770
shale	805
shale & lime	1745
sandy shale & lime	1790
shale & lime	2805
shale	2850
sandy shale	3010
sand	3114
sandy shale & lime	3160
shale & lime	3580
miss. chert	3612
lime	3860
Total Depth	

Scout Tops:	
Layton	3010
Kansas City	3170
Cherokee	3470
Miss.	3603 ?
Miss.	3606 ?
Simpson Sand	3836