

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- LARIO OIL & GAS CO.
 Farm- William Wolfe No. 1

SEC. 3 T. 35 R. 1E
 C SW SE

Total Depth. 3897'

Comm. 10-24-60


Comp. 11-8-60

Shot or Treated.

Contractor. Gearhart-Canaday Drilg. Co.

Issued. 12-17-6-

County Sumner
 KANSAS



Elevation. 1139' RB

Production. DRY

CASING:

8 5/8" 251' w/175 sx cem.

Figures Indicate Bottom of Formations.

surface soil	8	Chattanooga	3830
shale	130	Simpson sand	3854
shale w/lime	140		
lime	251		
lime w/shale stks	375		
shale	420		
lime	585		
shale, lime	750		
lime w/shale	990		
shale, lime	1240		
shale	1600		
shale, sand	1620		
shale w/lime	1785		
shale	1815		
lime	2000		
shale, lime	2090		
lime w/shale	2203		
shale	2286		
lime	2307		
shale	2454		
lime	2466		
shale	2500		
shale, sand	2581		
sand, Stalnaker	2725		
shale	2933		
sand	2970		
shale	2994		
sand, Layton	3052		
shale	3119		
lime, Kansas City	3224		
sand, Cleveland	3249		
shale	3300		
lime	3455		
shale	3489		
sand, sdy shale	3515		
shale	3560		
chat, Mississippi	3585		
lime	3741		
chert, lime	3762		
lime	3780		
shale	3853		
sand, Simpson	3898	RTD	
Total Depth			

OPS: SCOUT

Fuqua sand	1540
Tarkio	1622
Elgin sand	2062
Heebner	2143
Brown lime	2457
Stalnaker	2575
Layton Zone	2898
Kansas City	3112
B/Kansas City	3203
Cleveland sand	3222
Marmaton	3298
Cherokee	3421
Cherokee sand	3486
Mississippi	3563

