

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION

WELL COMPLETION OR RECOMPLETION FORM
ACO-1 WELL HISTORY

DESCRIPTION OF WELL AND LEASE

Operator: license # 5566
name Martindale Enterprises, Inc.
address 8222 Douglas #360
City/State/Zip Dallas, Texas 75225

Operator Contact Person Betty Dustin
Phone 918-273-3608

Contractor: license # 9341
name B. R. Walker Drilling

Well Site Geologist Don DeMoss
Phone 214-361-1680

PURCHASER Farmland Industries, Inc.

Designate Type of Completion

☒ New Well ☐ Re-Entry ☐ Workover

☐ Oil ☐ SWD ☐ Temp Abd
☐ Gas ☒ Inj ☐ Delayed Comp.
☐ Dry ☐ Other (Core, Water Supply etc.)

If OWWO: old well info as follows:

Operator
Well Name
Comp. Date Old Total Depth

WELL HISTORY

Drilling Method: ☐ Mud Rotary ☒ Air Rotary ☐ Cable

8-15-84 8-16-84 12-20-84
Spud Date Date Reached TD Completion Date

1235
Total Depth PBTD

Amount of Surface Pipe Set and Cemented at 137 feet

Double Stage Cementing Collar Used? ☐ Yes ☒ No

If Yes, Show Depth Set feet

If alternate 2 completion, cement circulated
from 0 feet depth to 1235 w/ 125 SX cmt

API NO. 15-125-26,800



*PT

County Montgomery

NW4 NW4 NE4 Sec 10 Twp 35S Rge 15
(location)

4855 Ft North from Southeast Corner of Section
2250 Ft West from Southeast Corner of Section

(Note: locate well in section plat below)

South East Tyro Project


Lease Name South Carnes Well# W-1

Field Name Hoot Owl

Producing Formation Bartlesville

Elevation: Ground KB

Section Plat



RECEIVED

STATE CORPORATION COMMISSION

JAN 17 1985

CONSERVATION DIVISION

Wichita, Kansas

WATER SUPPLY INFORMATION

Source of Water:

Division of Water Resources Permit #

☐ Groundwater. Ft North From Southeast Corner an
(Well) Ft West From Southeast Corner
Sec Twp Rge ☐ East ☐ West

☐ Surface Water. Ft North From Southeast Corner an
(Stream, Pond etc.) Ft West From Southeast Corner
Sec Twp Rge ☐ East ☐ West

☐ Other (explain)
(purchased from city, R.W.D. #)

Disposition of Produced Water: ☐ Disposal ☒ Repressuring

Docket # E-23,082

TUBING RECORD

size 2 3/8" set at 1080' packer at 1080' Liner Run ☐ Yes ☒ No

Date of First Production
SWI

Producing method

☐ flowing ☐ pumping ☐ gas lift ☐ Other (explain)

Estimated Production
Per 24 Hours

Oil

Gas

Water

Gas-Oil Ratio

Gravity

Bbls

MCF

Bbls

CFPB

METHOD OF COMPLETION

☐ open hole ☒ perforation

PRODUCTION INTERVAL

Disposition of gas: ☐ vented

☒ sold

1122-1140

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken

Samples Sent to Geological Survey

Cores Taken

☐ Yes

☐ No

☐ Yes

☐ No

☐ Yes

☐ No

Formation Description

☐ Log

☐ Sample

Name

Top

Bottom

shale	0-25	lime	850-867
sand	25-130	shale	867-896
shale	130-176	lime	896-903
lime	176-187	shale	903-1125
shale	187-425	sdv shale	1125-1135
lime	425-435	sand	1135-1165
shale	435-500	sdv shale	1165-1235
lime	500-537		
shale	537-555		
sdv shale	555-595		
shale	595-653		
lime	653-675		
shale	675-695		
sand	695-740		
shale	740-789		
lime	789-812		
shale	812-822		
lime	822-845		
shale	845-850		

CASING RECORD

☒ new

☐ used

Report all strings set - conductor, surface, intermediate, production, etc.

Purpose of string	size hole drilled	size casing set (in O.D.)	weight lbs/ft.	setting depth	type of cement	# sacks used	type and percent additives
surface	10"	7"	23	137	common	15	
production	6 7/16"	4 1/2"	9 1/2	1235	common	125	

PERFORATION RECORD

shots per foot specify footage of each interval perforated

Acid, Fracture, Shot, Cement Squeeze Record

(amount and kind of material used)

Depth

2	1122-1140		

Title **Secretary**

Date **1-4-85**

☐ Driller's Time Log Received

Distribution

☐ KCC

☒ SWD/Rep

☐ NGPA

☒ KGS

☐ Plug

☐ Other

By *[Signature]*
Rec.