



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

October 8, 1980

Exploration Services, Inc.
7 East Bijou
Suite 201
Colorado Springs, Colorado 80903

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Keith Trust Lease, Well No, 1, located in Section 5, T-35S, R-17E, Montgomery County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on October 1, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/tem

5 c to Colorado Springs, Colorado

OILFIELD RESEARCH LABORATORIES

LOG

Name Exploration Services, Inc. Lease Keith Trust Well No. 1

Depth Interval,
Feet

Description

CATTLEMAN SAND

544.0 - 549.0

Brown slightly calcareous sandstone.

549.0 - 550.0

Gray sandy shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Exploration Services, Lease Keith Trust Well No. 1
 Inc.

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	544.5	18.4	55	29	84	785	33.
2	545.5	17.2	54	29	83	721	32.
3	546.5	18.2	51	36	87	720	40.
4	547.5	18.1	49	45	94	688	47.
5	548.5	17.3	44	50	94	591	35.