

DS

Company

Farm Baldwin

No. 5

Sec. 2 T. 35 R. 18

Loc. 300 ft. from N. line

15 ft. lower than #4

1030 ft. from E. line

County Labette

Total Depth 1166


Comm. 4/23/26

Comp. 5/30/26

Shot or Treated

Contractor

Issued



Casing

20 in.

15 1/2

12 1/2

13 3/8

10 in.

8 1/4 802

6 5/8

5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

4	soil	4
1	white lime	5
28	brown sand	33
72	light shale	105
33	pink lime	138
5	black slate	143 some gas at 140
67	blue shale	210
39	Oswego lime	249
2	dark slate	251
30	Oswego lime	281
3	black slate	284 some gas at 284
11	brown lime	295 some gas at 295
3	dark shale	298
9	dark lime	307
28	blue shale	335
10	sandy shale	345 some gas from 336 to 346
9	blue shale	354
3	dark lime	357
8	light shale	365 total gas to this depth
5	blue shale	370 330,000 cu ft
8	dark lime	378 fishing job at 370, some
2	dark shale	380 gas at 378
6	dark lime	386
59	blue shale	445
20	sand squirrel	465
14	blue shale	479
10	black shale	489
28	light shale	517
28	dark shale	545
5	dark lime	550
45	black shale	595
13	Bartlesville sand	608
12	light shale	620
167	dark shale	787
1	Mississippi lime	788 500,000 ft. gas 150#, gas at 788
303	Mississippi lime	1090
1	green shale	1091
4	lime	1095
5	dark shale	1100 set 6 5/8 casing at 1100
12	dark shale	1112
5	blue sandy shale	1117
4	dark sandy lime	1121

(over)

(Cont.)

25	dark slate	1146
4	white sandy lime-	
	cap rock	1150 showing oil 1152½ to 1153½
4	light sandy lime	1154 showing of oil with
4	sandy lime	1158 oil sand mixed.
1.8	" " & oil sand	1159.8 good showing of oil
1.2	" " " "	1161 " "
5	white sandy lime	1166 no oil sand showing
	radium water at	1166 T.D.

2 pails coal in bottom of hole. Shut off good
5/14/1926. Some water at 885. 3 bailers to
a screw of lime 5/16/26.