


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. AYLWARD DRILLING CO.
Farm- Davis No. 1

SEC. 8 T. 35 R. 2E
SE SE NE

Total Depth. 3432
Comm. 4-29-55 Comp. 5-9-55
Shot or Treated Sand frac w/ 3000# sand, 220 BO
Contractor. Aylward Drilling Co.
Issued. 8-20-55

County Sumner
KANSAS



CASING:

8 5/8 89' w/ 100 sx cmt.
5 1/2 3418' w/ 250 sx cmt.

Elevation. 1146 DF

Production. 25 BOPD

Figures indicate Bottom of Formations.

sand & clay	40
clay & shells	105
sandy lime	110
lime & shale	180
shale & shells	340
red bed	360
shale & shells	405
shale & lime	515
red bed	530
shale	590
sand	610
lime	705
shale & lime	905
shale & shells	1260
shale & sandy lime	1350
shale	1500
shale & shells	1645
lime & shale	2356
sand & shale	2465
lime & shale	2740
shale	2765
sand & shale	2895
lime & shale	2985
lime	3070
sand & shale	3150
lime	3330
shale & lime	3355
lime	3432
Total Depth	

TOPS:
Stalnaker 2292
Kansas City 2972
Cleveland 3077
Oswego 3141
Bartlesville 3380
Mississippian 3395

DST #1: 2348-56, open 1 hr. rec. 50'
gas, 2' oil, 13' SO&GCM, 30' SW, BHP
875#

DST #2: 3419-32, open 1 hr. rec. tr.
free oil, 50' OCM, BHP 725#

Error in drill pipe tally move all
above tops and TD up the hole 7'.
TD would then be 3425

Drill plug & DD ; tst 9 BO, tr.W,
24 hrs. DD 3431, no inc. sand-frac,
tst 9 BO & 2 BWP/2 hrs.