


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company-LAURA JANE OIL COMPANY, INC,
Farm- Callender "B" No. 4

SEC. 9 T. 35 R. 2E
NW SE SW

Total Depth. 3393 Corr,
Comm. 6-27-56 Comp. 7-9-56
Shot or Treated.
Contractor. Laura Jane Oil Co., Inc.
Issued. 9-22-56

County Sumner
KANSAS



Elevation. 1131 KB

Production. 50 bbls

CASING:

8 5/8" 81'
5 1/2" 3380'

Figures indicate Bottom of Formations.

surface soil, shale	60
shale, anhydrite	235
shale, lime	310
red rock, shale	375
shale, lime	480
red rock	505
shale, lime	725
shale, shells	820
shale, lime	910
shale, shells	1175
shale, lime	2305
sand	2450
shale, lime	2561
shale	2732
sand	2810
shale, sand	2855
shale, lime	2910
shale, sdy lime	2939
lime	3022
shale, lime	3110
lime Oswego	3150
lime	3221
shale, lime	3354
sand	3361
shale	3369
congl. chert	3383
chat	3393 Corr.
Total Depth	RTD

Tops:

Natan lime	2261
Stalnaker sand	2305
Layton sand	2728
Kansas City lime	2926
Oswego lime	3109
Burgess sand	3350 Corr.
Mississippian "Chat"	3373 Corr.