

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company. HOLIDAY OIL & GAS CO.  
Farm- Dean "A" No. 3

SEC. 12 T. 35 R. 2E  
NE SE NW

Total Depth. 3550'  
Comm. 7-30-57 Comp. 8-8-57

County Sumner  
KANSAS

Shot or Treated.  
Contractor. Harold Martin Drlg. Co., Inc.  
Issued. 11-2-57



CASING:  
8 5/8" 204' w/175 sx cem.  
5 1/2" 3549' w/75 sx cem.

Elevation. 1196

Production. 25 BOPD

Figures indicate Bottom of Formations.

clay-shale	60
sand	70
sand-shale	90
shale-shells	160
lime-shale	205
lime-shale stks	214
lime-shale	240
sand shale-lime	330
brkn lime-shale	375
shale	420
lime	490
red rock-shale	510
lime-shale stks	730
shale-red rock	805
lime-shale	880
shale-lime stks	1175
shale-lime-red rock stks	1250
sand-shale	1300
shale	1440
shale-lime stks	1505
lime-shale	1575
shale-lime stks	1640
lime-shale	2020
shale-lime stks	2318
lime-shale	2363
sand Stalnaker	2420
shale-sand	2560
shale-lime stks	2691
shale-lime	2826
shale	2827
sand Layton	2860
shale-sand	2920
shale	2947
shale-lime stka	3030
Kansas City lime	3045
lime Kansas City Zone	3114
shale-lime	3153
sand-shale	3162
shale-lime	3216
Oswego lime	3287
lime-Oswego Zone	3334
lime-shale stks	3362
shale-lime	3497
shale	3507
sand	3512
Bartlesville sand	3522
Mississippi	3537
Mississippi lime	3550
Total Depth	

TOPS:

Layton sandstone	2820
Kansas City limestone	3012
B/Kansas City	3115
Cleveland Zone	3146
Oswego limestone	3210
Cherokee shale	3321
Bartlesville sand	3506
Mississippi lime	3538