

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

State Geological Survey

API No. 15 — 191

21264 WICHITA BRANCH


County Number

S. 14 T. 35S R. 2E

Loc. c of SW 1/4 SE 1/4

County Sumner

640 Acres
N



Elev.: Gr. 1100±

DF KB

Operator Mark Ganer Oil & Gas

Address P.O. Box 195, Tonkawa, OK 74653

Well No. #4 Lease Name Clark

Footage Location 660 South feet from (N) (S) line 1980 East feet from (E) (W) line

Principal Contractor Lewis Exploration Geologist

Spud Date 5/10/81 Date Completed 5/11/81 Total Depth 890 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser Newkirk Gas Transmissions, Inc.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 5/8	7"	20	250	Reg.	50	3% CC
L.S.	6 1/4	2 7/8	6.4	890	Reg. & Pos. Mix	100	10% NaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		840-852

Size	Setting depth	Packer set at
3/4"	837	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gal 20% MCA	840-852
500 gal 28% Mod	840-852

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS Oil Gas Water

bbls. 50 MCF 1.5

Disposition of gas (vented, used on lease or sold) Sold

Producing interval(s)

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1981

CONSERVATION DIVISION
Wichita, Kansas

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Mark Ganer Oil & Gas		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #4	Lease Name Clark	Gas
S 14 T 35SR 2E E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Hotson Sand	726	739	Hotson	
Lime - White	836	908 1?	Neva	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Title
	10/7/51 Date