

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- E.H. RIGGS
Farm- Wentworth

No. 2

SEC. 4 T. 35 R2E
 SE SE SW

Total Depth. 3458'
Comm. 8-16-56 Comp. 8-26-56
Shot or Treated.
Contractor. Capitt Drlg. Inc.
Issued. 10-13-56

County Sumner
KANSAS



CASING:

8 5/8" 92' w/80 sx cem.
5 1/2" 3440' w/75 sx cem.

Elevation. 1164' KB

Production. 25 BOPD

Figures indicate Bottom of Formations

shale-lime	200
shale-shells	340
shale-ssshells	470
shale-lime	1020
shale-lime strks	1310
shale-lime	1890
shale-lime shells	2245
shale-sdy shale	2328
Core #1	2369
sand	2390
Core #2	2413
sand	2456
sand-shale	2545
shale-lime shells	2775
Layton sand	2845
shale-sand	2910
shale-lime	2975
lime	3100
shale-lime	3205
lime	3265
shale-lime	3325
shale-sdy shale	3421
chat	3425
Core #3	3435
shale-lime	3440
Core #4	3453
Chert	3458
Total Depth	RTD

TOPS:

Brown lime	2293
Stalnaker Zone	2333
2nd Stalnaker	2348
Lower Stalnaker	2391
Layton	2775
Kansas City	2973
Cleveland Zone	2083-3100
Oswego	3156
Mississippi	3421

Core #1 - 2328-69
Core #2 - 2390-2413
Core #3 - 3425-3435
Core #4 - 3440-3453

DST #1 - 3435-3453 (in core hole)
Open 1 hr., good blow, rec. 324'
fas, 70' GCM, tr oil, no wtr.
IFP 33#, FFP 50 #, B HP 370# in
20 min. pressure still building.

DST #2 - 3435-3458 2 hrs., gas to ..
surface in 2 hrs., rec. 245' fluid,
gas & OCM. No free oil. No wtr.
IFP 33#, FFP 70#, BHP failed to
record.