


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

SINCLAIR PRAIRIE OIL CO.  
Harold Herrick No.7.

SEC.15 T.35 R. 2 E  
SW NE NE  
330'f SL 330'f WL NE $\frac{1}{2}$ NE $\frac{1}{4}$

Total Depth. 3470' SIM  
Comm. 8-29-42 Comp. 10-4-42  
Shot or Treated. 60 Qts. 9-26-42 3436-54  
Contractor. Harbar Drlg. Co.  
Issued. 1-2-43

County. Sumner



CASING:

10 $\frac{3}{4}$ " 67' Cem. LI  
7" 3412' Cem. LI  
23/8" 3454' LI

Elevation.

Production. Pot. 173.28 B.

Figures Indicate Bottom of Formations.

|                     |      |                   |
|---------------------|------|-------------------|
| surface clay        | 10   | Producing from    |
| shale & shell       | 60   | Bartlesville Sand |
| lime                | 82   | 3410-50           |
| lime & shale        | 220  |                   |
| shale & shells      | 586  |                   |
| lime & shale        | 705  |                   |
| shale & lime shells | 855  |                   |
| shale & shells      | 1120 |                   |
| lime & shale        | 1275 |                   |
| shale & lime shells | 1495 |                   |
| lime                | 1585 |                   |
| shale & shells      | 1620 |                   |
| lime                | 1640 |                   |
| lime sdy            | 1660 |                   |
| lime & shale        | 1905 |                   |
| shale               | 2120 |                   |
| lime sdy            | 2130 |                   |
| shale               | 2148 |                   |
| sdv lime & shale    | 2192 |                   |
| shale               | 2287 |                   |
| sand & lime         | 2306 |                   |
| shale               | 2340 |                   |
| sand                | 2365 |                   |
| shale               | 2695 |                   |
| shale & sand        | 2762 |                   |
| sand                | 2898 |                   |
| shale               | 2980 |                   |
| shale & lime        | 3075 |                   |
| lime sdy            | 3090 |                   |
| shale               | 3155 |                   |
| lime                | 3300 |                   |
| shale               | 3410 |                   |
| shale & sand        | 3428 |                   |
| sand                | 3450 |                   |
| chat                | 3470 |                   |
| Total Depth. - SIM  |      |                   |

1st 24 hrs after shot 50 B.  
2nd 24 hrs after shot 63 B.  
Potential 173.28 Bbls.

Core Record: 3390-3428  
two cores

Bartlesville 3410-50  
Chat 3450-70