

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - SINCLAIR PRAIRIE OIL CO.
Farm - Herrick No. 8

SEC. 15 T. 35 R. 2E
SWc NE
330'f SL 330'f WL NE $\frac{1}{4}$

Total Depth. 3453' PB 3451'
Comm. 11-2-45 Comp. 11-30-45
Shot or Treated. Acidized w/43 qts.
Contractor. Harbor Drlg. Co.
Issued. 5-3-47

County. Sumner

KANSAS



CASING:

10 3/4" 68' cem. w/50 sx. 2 3/8" 3433'
7" OD 3302' cem. w/150 sx. 3/4" 3425'

Elevation. _____

Production. Est. 40 Bbls.

Figures Indicate Bottom of Formations.

clay-shale	15
shale-shells	50
lime	80
anhydrite	125
anhydrite & shale	180
shale & lime	337
shale	405
lime & shale	720
shale & red bed	832
shale-lime	1015
shale	1045
shale & shells	1720
shale-lime	2165
lime & shale sdy	2255
lime & shale	2770
sand & shale	2847
shale sdy	2885
lime & shale	3190
lime	3305
shale & lime	3380
Coreing	3433
lime	3434
chat	3453 PB 3451
Total Depth	

Oil & gas From 3443-3451

Plugged hole back to 3451 using 1' lead
wool & 1' lime rock.

Tops:

Bartlesville 3385-3429
Chat 3434-3451

Drilled to 3453'
Plugged back w/lead wool to 3452'
Plugged back w/lime rock to 3451'
3385-3429 Bartlesville Sand-Only
small show oil.
3434' reduced hole to 6 3/4"
No liner set in well
Chat 3434-3451 swabbed after shot
37 bbls. oil, 1 bbl. wtr.

Well is pumped w/D-130 National Jack
Pumping 2' from btm. 16' 2 1/2" anchor
on tubing. 2"x9' BMW Admore
stationary outside tube pump
80' American angle iron derrick.

Acid Record:

20 Qts. 3451 up to 3441
3 Qts. 3441 up to 3429
20 Qts. 3429 up to 3415