

NW NW SW SE
(NAD 83 - KGS-ORL 2022)

KANSAS DRILLERS LOG

S. 4 T. 35 R. 20 E. 21 E
Loc. 280' FWL & 1000' FSL SE
County Labette

API No. 15 — 099 — 20,863
County Number

Operator
S & S Oil Co.

Address
Box 304 Oswego, Kansas 67356


Well No. #3 Lease Name Ruby Schreppel

Footage Location
1000' FSL feet from (N) (S) line
280' FWL feet from (E) (W) line

Principal Contractor M & M Drilling Co. Geologist Bill Kardos

Spud Date 11-10-78 Total Depth 650' P.B.T.D. N/A

Date Completed 11-12-78 Oil Purchaser None



Locate well correctly
Elev.: Gr. 910'
DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/2	7"	14	50'	Portland	10	None

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
None					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	bbis.	MCF	bbis.		
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
			None		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

Operator S & S Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 3	Lease Name Schreppel	Dry
S <u>4</u> T <u>35</u> R <u>20</u> <u>E</u>		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Overburden	0	4		
Gray lime	4	33		
Black shale	33	38		
Gray lime	38	66		
Black shale	66	69		
Gray lime	69	71		
Gray sand	71	73		
Gray shale	73	172		
Black shale	172	176		
Gray shale	176	181		
Gray sandy shale	181	192		
Gray shale	192	240		
Sandy shale	240	270		
Gray shale	270	307		
Gray sand	307	323		
Black shale	323	334		
Gray sand	334	342		
Gray sandy shale	342	354		
Dark gray shale	354	395		
Lt. gray sand	395	404		
Black shale	404	407		
Brown lime	407	409		
Dark gray shale	409	522		
Dark gray shale	522	604		
		604	Top Miss.	
Miss. Lime & sand	604	650		
		650	T.D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Rudy Schreppel Jr.</i>
	Signature
	Co-Owner
	Title
	12-18-80
	Date