

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 099 — 21,187
County Number

Operator

S & S Oil Company

Address

Box 304 Oswego, Ks. 67356

Well No.

10

Lease Name

Stan Lips

Footage Location

1250' FNL

feet from (N) (S) line

450' FEL

feet from (E) (W) line

Principal Contractor

Blazer Drilling Company

Geologist

Bill Kardos

Spud Date

4-10-80

Date Completed

4-12-80

Total Depth

626'

P.B.T.D.


N/A

Directional Deviation

None

Oil and/or Gas Purchaser

None

SW SE NE SW
(NAD 83 KGS-122-0000) 21
35 20
S. 5 T. 20 R. 35 E
Loc. 1250' FNL-450' FEL of SW 1/4
APP E/2 E/2 SW
County Labette640 Acres
N

Locate well correctly

901'

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/2	7"	14	55'	Portland	12	None

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

to	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
None					
DATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPS	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
			None		

INSTRUCTIONS: As provided in KCC Rule 82-2.125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-532-2205. If confidential custody is desired, please note

Operator S&S S & S Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 10	Lease Name Stan Lips		Dry
S <u>5</u> T <u>35</u> R <u>20</u> ^E			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored interval, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Overburden	0	3	
Lime	3	26	
Black shale	26	29	
Sandy lime	29	42	
Lime	42	68	
Sand	68	76	
Sandy shale	76	119	
Dark gray shale	119	153	
Sandy lime	153	159	
Sand	159	165	
Sandy shale	165	174	
Dark gray shale	174	183	
Dark gray shale	174	183	
Lime	183	189	
Dark gray shale	189	271	
Sandy shale	271	289	
Dark gray shale	289	343	
Sand	343	352	Bartls.
Dark gray shale	353	355	
Sandy shale	355	360	
Dark gray shale	360	402	
Sand	402	405	
Shale	405	407	
Dark gray shale & streaks of lime	407	617	Top Miss.
Miss. Lime	617	626	T.D.
		626	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Co-Owner Title 12-22-80 Date		

911205