

SE DE NW NE
(NA083 KLS ORL 2022)

KANSAS DRILLERS LOG

S. 6 T. 35S R. 20E^E_W
 Loc. 1200' FWL 1200' FNL NE 1/4
 County Labette

API No. 15 — 099 — 20850
 County Number

Operator S&S Oil Co.

Address Box 304 Oswego, Ks. 67356

Well No. #6 Lease Name John R. Filson

Footage Location 1200' FNL 1200' FWL
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Nance Drilling Company Geologist Bill Kardos

Spud Date 3-14-79 Total Depth 1001' P.B.T.D. N/A

Date Completed 4-2-79 Oil Purchaser

640 Acres
N

Locate well correctly
Elev.: Gr. 896.5'
DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/2	7"	14	50'	Portland	10	None
Intermediate	6 1/2	4 1/2"	9	960'	Portland	105	None

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None-Packer shoe drilled out.	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.		MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator S & S Oil Company DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 6 Lease Name John Filson FWDW

S 6 T35 R 20 E

WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Table with 5 columns: FORMATION DESCRIPTION, CONTENTS, ETC., TOP, BOTTOM, NAME, DEPTH. The table is currently empty.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received Rudy Schepel Jr. Signature Co-Owner Title 11-18-80 Date

FROM	TO	KIND OF ROCK	REMARKS	FROM	TO	KIND OF ROCK	REMARKS
0	4	overburden		179	181	Black Shale	
4	18	Lime		181	201	Gray Shale	
18	24	Dark Gray Shale		201	209	Black Shale	
24	30		sand	209	230	Dark Gray Shale	
30	47	Lime		230	253	Gray Shale	
47	49	Black Shale		253	255	Dark Brown Lime	
49	54	sandy Lime		255	258	Gray Shale	
54	65	Light Gray shale	sand	258	262	Gray Sand	
65	74	Dark Gray sandy Shale		262	270	Gray Sandy Shale	
74	138	Dark Gray Shale		270	302	Dark Gray Shale	
138	141	Brown Sandlime		302	312	Gray Shale	
141	151	Gray Shale		312	314	Dark Gray Sand	
151	166	Brown Sandy Lime		314	330	Dark Gray Shale	
166	174	Dark Gray Shale		330	338	Gray Sand (show of oil)	
174	179	Dark Brown Lime		338	390	Gray Shale	
390	399	Light Gray Sand		911	919	Lt Gray Lime	
399	600	Dark Gray Shale		919	923	Green Shale	
600	612	Brown Sandy Lime MISS. Lime		923	935	Lt. Brn. Lime	
612	613	Chert		935	941	Green Shale	
613	615	Brn. Sandy Lime		941	947	Lt. Brn. Lime Streaks of Brn. Shale	
615	650	Gray Sandy Streaks of White Lime		947	950	Green Shale	
650	654	White Lime		950	960	Drk. Gray Shale	
654	741	Brown Lime (Chert)		960	970	Black Shale Brn. Lime	
741	768	White Lime		970	972	Iron	
768	820	Blue Chert Brown Lime		972	976	Brn. Lime (Arb. 972-973)	
820	834	Brown Sandy Lime Blue Chert		976	1000	Brn. Lime Chert	
834	885	BRN Lime Blue Chert			1000	T. D.	
885	896	Gray Lime Chert					
896	897	Green Shale					
897	911						