

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 099 — 20,652
County Number

Operator

S & S Oil Co.

Address

Box 304 Oswego, Kansas 67356

Well No.

#3

Lease Name

John R. Filson

Footage Location

400' FNL

feet from (N) (S) line

400' FNL

feet from (E) (W) line

Principal Contractor

Nance Drilling Co.

Geologist

Bill Kardos

Spud Date

9-11-77

Date Completed

10-25-77

Total Depth

615

P.B.T.D.

N/A

Directional Deviation

None

Oil and/or Gas Purchaser

Cities Service Gas Co.

SE NW NW NE
(M083 KCS DRL 0022)

WICHITA, BRANCH


S. 6 T. 35 R. 20 E W

Loc. 400' FNL & 400' FNL NE

County Labette

640 Acres

N



Locate well correctly

Elev.: Gr. 904.92

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Top Casing	8 1/2	7"	14	50'	Portland	10	none
Production	8 1/2	7"	14	50'			

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	615'	583'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
None Shut-In					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rudy Schreppel, Jr.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 3	Lease Name Filson	Gas
S 6 T35 R 20 E *		

WELL LOG			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Overburden	0	6		
Gray Lime	6	18		
Black Shale	18	25		
Gray Lime	25	43		
Gray Shale	45	55		
Black Shale	55	120		
Dark gray shale	120	135		
Brown sand	135	140		
Gray shale8	140	158		
Brown sand	158	162		
Soft gray shale	162	175		
Brown lime	175	179		
Gray shale	179	183		
Black shale	183	195		
Gray shale	195	295		
Lgt. gray shale	295	319		
Gray sand & oil	319	322		
Black shale	322	335		
Gray sand	335	341		
Dark gray shale	341	370		
Black shale	370	385		
Lgr. gray sandy shale	385	398		
Black shale	398	405		
Gray shale	405	410		
Dark Gray shale	410	465		
Med. gray shale	465	515		
Lgt. gray shale	515	529		
Med. gray shale	529	580		
Black shale	580	589		
Dark gray shale	589	594		
		594	Top Miss.	
Miss. chat	594	615	T.D.	
		615		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Rudy Schreppel Jr. Signature Co-Owner Title 11-18-80 Date
---------------	---

52432