


WELL COMPLETION REPORT AND DRILLER'S LOG

State Geol  
WICH

Survey  
S. 6 T. 35 R. 20 E  
Loc. 300' FEL 200' FSL N 1/2 N  
SE SE NE NW  
County Labette

API No. 15 — 099 — 21,211  
County Number

Operator S & S Oil Company  
Address Box 304 Oswego, Ks. 67356  
Well No. 10 Lease Name Jack Foley  
Footage Location 200' FSL 4160 FSL 2940 FGL 300' FEL  
feet from (N) (S) line KCC Record feet from (E) (W) line  
Principal Contractor Nance Drilling Company Geologist Bill Kardos  
Spud Date 5-12-80 Date Completed 5-15-80 Total Depth 365' P.B.T.D. N/A  
Directional Deviation None Oil and/or Gas Purchaser Koch Oil Company



Locate well correctly  
Elev.: Gr. 907'  
DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/2	7"	14	55'	Portland	12	None
Intermediate	6 1/2	4 1/2	9	360'	Portland	65	None

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	1/2	321' - 334'

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
100 Gals. 15% acid	321' - 334'
14 sx 20-50 sand, 30 sx 16-40 sand, 15 sx 10-20 sand.	321' - 334'

INITIAL PRODUCTION

Date of first production 5-16-80 Producing method (flowing, pumping, gas lift, etc.) Flowing  
 RATE OF PRODUCTION PER 24 HOURS  
 Oil 17 bbls. Gas 170 MCF Water 3 bbls. Gas-oil ratio CFPB  
 Disposition of gas (vented, used on lease or sold) Cased In Producing interval(s) 321' - 334'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator S & S Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 10	Lease Name Jack Foley	Oil
S 6 T 35 R 20 E JFK		

FROM	TO	KIND OF ROCK	REMARKS	FROM	TO	KIND OF ROCK	REMARKS
0	6	OVERBURDEN		333	343	<del>BURTS</del> SAND (338-343 <del>gray shale</del> )	
6	21	LIME		343	348	SHALE	
21	26	DRK GRAY SHALE		348	352	SANDY SHALE	
26	49	LIME & streaks of shale		352	400	DRK GRAY II streaks of lime	
49	55	SANDY LIME		400	405	GRAY SAND	
55	80	II	SHALE	405	603	DRK GRAY SHALE streaks of lime	
80	150	GRAY II		603	667	MISS LIME SANDY LIME	
150	167	SAND		667	685	BRN LIME CHERT	
167	176	SHALE		685	707	DRK BRN LIME CHERT	
176	179	LIME		707	885	BRN LIME CHERT	
179	204	SHALE		885	934	GRAY LIME CHERT	
204	308	SHALE streaks of lime		934	939	GREEN SHALE	
308	312	SANDY SHALE		939	942	BRN II	
312	328	DRK GRAY II		942	947	GRAY LIME	
328	333	BLACK SHALE		947	951	II SHALE	

FROM	TO	KIND OF ROCK	REMARKS
951	954	DRK GRAY	SANDY LIME
954	959	BRN	SHALE
959	970	BLACK II (CHATANOGA)	
970	972	CAP	ROCK
		972	TD

6-35 20E  
#9 Jack Foley

RY, TO COMPLETE WELL RECORD.

*Judy Schappel Jr*  
Signature

Co-Owner  
Title

11-18-80  
Date