

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 099 — 21,213
County Number

Operator

S & S Oil Company

Address

Box 304 Oswego, Ks, 67356

Well No.

12

Lease Name

Jack Foley / KCC Record

Footage Location

500' FNL 4780 FSL 1/3690 FEL 1050' FEL
feet from (N) (S) line feet from (E) (W) line

Principal Contractor

Blazer Drilling Company

Geologist

Bill Kardos

Spud Date

5-17-80

Date Completed

5-19-80

Total Depth

403'

P.B.T.D.

N/A

Directional Deviation

None

Oil and/or Gas Purchaser


Koch Oil Company

WICHITA, BRANCH

S. 6 T. 35 R. 20 E

Loc. 500' FNL 1050' FEL N¹/₂ NW
SW NW NE NW - KCC Record

County Labette

640 Acres
N

Locate well correctly

Elev.: Gr. 896'

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/2	7"	14	55'	Portland	12	None
Intermediate	6 1/2	4 1/2	9	400'	Portland	126	None

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	1/2	304'-322'
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
150 Gals. 15% acid	304'-322'
10 sx 20-50 sand, 40 sx 16-40 sand, 18 sx 10-20 sand.	304'-322'

INITIAL PRODUCTION

Date of first production 8-12-80		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil 2	Gas None	Water 6	Gas-oil ratio CFPB
		bbls.	MCF	bbls.	
Disposition of gas (vented, used on lease or sold)				Producing interval (s) 304'-322'	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator S & S Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 12	Lease Name Jack Foley	Oil
S <u>6</u> T <u>35</u> R <u>20</u> ^E _W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Overburden	0	2		
Lime	2	10		
Black shale	10	15		
Sandy Lime	15	18		
Black shale	18	40		
Gray sandy shale	40	103		
Dark gray shale	103	122		
Lime	122	124		
Gray shale	124	138		
Sand	138	150		
Gray sand	150	156		
Dark gray shale	156	166		
Lime	166	172		
Dark gray shale	172	203		
Gray shale	203	304		
Sand (good show oil)	304	323	Barts.	
Shale	323	330		
Sand gas	330	332		
Sand oil	332	337		
Dark gray shale	337	403		
		403	T.D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature <i>Rudy Schreppel Jr.</i> Co-Owner Title 11-18-80 Date
---------------	---