


KANSAS DRILLERS LOG

S. 6 T. 35 R. 20 ^E/_W
 Loc. 800' FWL & 400' FSL SE

County Labette

640 Acres
N



Elev.: Gr. 895'

DF _____ KB _____

API No. 15 — 099 — 20,772
 County Number

Operator
S & S Oil Company

Address
Box 304 Oswego, Kansas 67356

Well No. # 1 Lease Name Henry A. Tunget

Footage Location 400' FSL 800' FWL
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Nance Drilling Company Geologist Bill Kardos

Spud Date 4-18-78 Total Depth 623 1/2' P.B.T.D. N/A

Date Completed 4-21-78 Oil Purchaser None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/2"	7"	14	50'	Portland	10	None

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production <u>None</u>		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) <u>None</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

22413

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Operator S & S Oil Company

Well No. 1 Lease Name Tunget Dry

S 6 T 35 R 20 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Overburden	0	3		
Lime	3	25		
Dark gray shale	25	34		
Lime	34	55		
Black shale	55	60		
Gray sand	60	87		
Dark gray sandy shale	87	115		
Dark gray shale	115	148		
Sand	148	152		
Dark gray sandy shale	152	169		
Dark gray sand	169	172		
Dark gray shale	172	188		
Lime	188	193		
Black shale	193	197		
Dark gray shale	197	226		
Coal	226	228		
Dark gray shale	228	316		
Dark gray sand	316	323		
Dark gray shale	323	349		
Gray sand	343	349		
Dark gray sandy shale	349	366		
Dark gray shale	366	412		
Lime	412	414		
Dark gray shale	414	614		
		614	Top Miss.	
Miss. Lime	614	623 1/2		
		623 1/2	T.D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature: *Rudy Schappel Jr.*

Title: Co-Owner

Date: 12-18-80