

KANSAS

NE NE SEC 3  
(NAD83 KGS DEL  
2022


**WELL COMPLETION REPORT AND  
DRILLER'S LOG**

S. 6 T. 35 R. 20 <sup>E</sup><sub>XX</sub>

Loc. 1383' FNL 161' FNL SE  $\frac{1}{4}$

County Labette

640 Acres  
N



Locate well correctly

Elev.: Gr. 888'

DF \_\_\_\_\_ KB \_\_\_\_\_

API No. 15 — 099 — 21,183  
County Number

Operator

S & S Oil Company

Address

Box 304 Oswego, Ks. 67356

Well No.

5

Lease Name

Henry A. Tunget

Footage Location

1383' F.N.L.  
feet from (N) (S) line

161' F.W.L.  
feet from (E) (W) line

Principal Contractor

Blazer Drilling Company

Geologist

Bill Kardos

Spud Date

3-31-80

Date Completed

4-7-80

Total Depth

651'

P.B.T.D.

N/A

Directional Deviation

None

Oil and/or Gas Purchaser

Cities Service Gas Co.

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 $\frac{1}{2}$	7"	14	55'	Portland	10	None
Production Gas	6 $\frac{1}{2}$	2 $\frac{3}{8}$	7 $\frac{1}{2}$	640'	Portland	118	None

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	$\frac{1}{2}$	601' - 608'

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
100 Gals. 15%	601' - 608'

**INITIAL PRODUCTION**

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
None Shut-In					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator S & S Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 5	Lease Name Henry Tunget	Gas
S <u>6</u> T <u>35</u> R <u>20</u> E <u>X</u>		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Overburden	0	3		
Lime	3	11		
Dark gray shale	11	16		
Lime	16	50		
Gray sand	50	64		
Sandy shale	64	117		
Dark gray shale	117	152		
Sand	152	159		
Dark gray shale	159	174		
Lime	174	181		
Dark gray shale	181	252		
Gray shale	252	301		
Gray sand	301	311		
Gray shale	311	332		
Gray sand show of oil	332	337		
Gray shale	337	377		
Dark shale streaks of lime	377	391		
Sand	391	400		
Dark gray shale streaks of lime	400	600		
Lime	600	602		
		602	Top Miss.	
Sandy lime	607	651		
		651	T.D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Rudy Schappel Jr.</i>
	Signature
	Co-Owner
	Title
	11-18-80
	Date