


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BOWMAN AND GRISAMORE
 Farm- Barton No. 5

SEC. 6 T. 35 R. 3E
 SW NE SW

Total Depth. 3512'
 Comm. 7-3-56 Comp. 7-12-56
 Shot or Treated.
 Contractor. Criswell Drilling Company
 Issued. 11-24-56

County Cowley
 KANSAS



Elevation. 1208' RB

Production. 25 BOPD

CASING:

8 5/8" @345'

Figures indicate Bottom of Formations

ALL MEASUREMENTS K. B.

lime & lime shells & red bed	345
shale, red bed & shells	580
shale & lime shells	825
shale & lime	1000
shale & shells	1325
shale & lime strks	1535
shale With lime	1660
shale & lime	1890
shale & lime, sandy	1950
shale with lime strks	2005
shale	2318
sand & shale strks	2435
shale w/sand strks	2450
shale w/lime	2515
shale & lime	2790
sand & sandy shale	2875
shale & sandy shale	2907
shale & lime	2953
shale & lime, sandy	2993
lime, Kansas City	3018
shale & sand	3117
sand	3135
shale & sandy shale	3186
lime	3298
lime & shale strked	3390
shale	3470
sand	3500
shale	3512

Total Depth

SCOUT TOPS	
Layton	2775
Layton Sand	2783
Kansas City	2968
Oswego	3185
Cattleman Sand	3396
Bartlesville	3460
Bartlesville Sand	3485