

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bk Bldg., Wichita, Kansas.

J. K. S.


ALMA OIL CO. ET AL.  
Marguerite Lowe No. 3.

SEC. 6 T. 35 R. 3E  
SEcSE

AUG 15 1936

Total Depth. 3550' P.B. 3120'  
Comm. 4-22-36 Comp. 5-21-36  
Shot or Treated.  
Contractor.  
Issued. 8-15-36

County. Cowley



CAS ING:

12 1/2"  
7 "

117'  
3442'

Elevation.

Production. Est. 15 Bbl.

Figures Indicate Bottom of Formations.

sand & shale	115	sand, showing soft gas	3115
shale & sand	145	lime & shale	3122
shale & shells	265	shale & lime shells	3153
broken lime	280	shale & shells	3170
red bed, shale & shells	312	lime & shale	3185
shale & lime	548	lime sdy	3204
lime	564	lime	3242
red bed .	582	lime	3296
lime & shale	700	lim & shale	3300
red bed & shale	780	broken lime	3325
lime & shale	1011	lime	3345
shale & shells	1274	shalo	3435
lime	1283	red rock	3440
lime & shale	1458	sand	3443
lime	1489	sdv shale	3505
shale & lime	1600	red rock & shale grey	3510
broken lime	1700	red rock & shale	3514
shale & lime	1895	lime	3550
lime	1910	Total Depth	
lime & shale	1962		
brown shale & lime	2085		
shale & lime	2150		
shale	2224		
shale & shells	2315		
sand & shale	2450		
shale blue	2494		
shale tough	2526		
shale blue	2557		
shale & lime	2580		
shale	2763		
shale & sand	2885		
broken lime	2910		
sdv shale	2955		
broken lime	2973		
limo & shalo	2998		
broken lime	3070		
shale blue & shells	3079		
limo	3090		

Well plugged back from 3550' to 3120'.  
Perforated from 3085' to 3109', casing.