


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location NE NW SW Sec. 18 T. 35 R. 3E.  
300' fr NL 1020' fr WL.

Casing Record  
10" Farm- Gally No. 1  
20" 8 1/2" Company- Roxana Petr. Corp.  
15 1/2" 65/8" Contr.-  
12 1/2" 53/16" Comm.- 11/23/25. Comp.- 11/4/1928.  
Total Depth 2221' Shot Quarts Between.  
Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations. Initial Production 200,000' Cu.  
Date Issued. 12/1/1928 DEEPENING RECORD. Comm. 9/21/1928. Ft. Gas - 135# R.P.  
Elevation 1187  
When started deepening. D&A After Deepening

Formation	Depth	Formation	Depth	Formation	Depth
clay	30	shale	1150	lime	1995
sand HFW	80	lime	1155	red rock	2010
shale	150	shale	1160	sand	2015
lime 5 BW	165	lime	1170	3,100,000' Gas.	
shale 20" 177'	185	shale	1180		
lime	195	lime	1185		
shale	210	shale	1200		
lime	280	lime	1205		
shale	370	shale	1220	SIM	2019
lime	375	lime	1230	Gas 200,000'. -135# R.P.	
shale	380	shale	1245	sand hole caving	2023
lime 3 BW	435	lime	1255	sand & shale caving	2060
red rock	470	shale	1265	shale	2065
lime	485	lime	1285	shale & lime	2070
shale	490	shale	1310	lime	2085
lime	500	lime	1320	shale	2090
red rock	505	shale	1325	red & green shale	2098
lime	515	lime	1360	sandy lime	2105
sandy lime	535	shale	1365	limy shale	2112
lime HFW	570	red rock	1370	sand	2128
red rock	585	shale	1410	shale	2140
15 1/2" 580'		lime	1425	shale & lime	2155
lime	600	shale	1430	limy sand	2180
shale	605	lime	1435	sandy lime	2195
lime	650	shale	1440	sand	2220
shale	655	lime	1460	1/2 BW PH 2215-20'	
lime	680	shale	1465	2220-2221' SIM	
shale	685	lime	1480		
lime	690	shale	1490	Total Depth	2221'.
shale	705	lime	1500		
red rock	735	shale	1510	Hole caved most of the	
lime	750	lime	1520	time	
red rock	770	shale	1525		
lime	835	lime	1530		
Gas 775' 1 M.		shale	1580		
shale	840	lime	1590		
lime	895	shale	1605		
shale	910	lime	1630		
lime	920	shale	1640		
shale	925	lime	1690		
lime	935	shale	1695		
shale	945	lime	1705		
lime	955	shale	1710		
12 1/2" 960'		lime	1780		
shale 5 BW PH	995	shale	1785		
lime	1000	lime	1790		
shale	1030	shale	1855		
lime	1045	sandy lime	1870		
shale	1050	lime	1875		
lime	1070	sandy lime HFW	1885		
shale	1075	lime	1890		
lime	1085	shale	1950		
shale	1095	10" 1885'			
lime	1110	lime	1960		
shale	1115	shale	1970		
lime	1130	slate	1985		