

300 East Main Street
Wichita, Kansas

FEB 7 1970

CASING RECORD

8 5/8	210' Cemented w/150 sacks
5 1/2	3383' Cemented w/200 sacks
T. D.	3390'

KELLY BUSHING MEASUREMENT 5' ABOVE GROUND LEVEL.

FORMATION	DEPTH
Shale & Lime	0-210
Shale & Lime stks.	350
Lime & Shale	660
Shale & Lime	1220
Sdy. Shale	1495
Shale & Lime stks.	1785
Shale	2015
Shale & Sands	2256
Lime	2170
Shale	2184
Sand & Shale	2292
Shale	2637
Sand	2762
Shale	2826
Lime	2944
Sand	2962
Shale	3030
Lime	3152
Shale	3240
Sand	3250
Shale	3380
Lime	3390

TOPS

Layton	2637
Kansas City	2826
Cleveland	2944
Marmaton	3030
Cattleman	3240
Mississippi	3380

3-35-3E
NE NW SW

Location: NE/4 of NW/4 of SW/4
Section: 3-35S-3E
Cowley County, Kansas
Farm: Brandenburg #1
Well Owner: Comet Petroleum Co.
Contractor: WHITE & ELLIS DRILLING,
Commenced: 12-9-69
Completed: 12-17-69

Cor. 1154 KB

20 BOPD