

**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock,                      Wichita, Kansas

Company- H. H. BLAIR  
 Farm- Sleeth

No. 1

SEC. 12 T. 35 R. 5E  
 C NW NE

Total Depth. 3713'

Comm. 1-14-61

Comp. 1-31-61


Shot or Treated.

Contractor. Red Drlg. Co.

Issued. 3-25-61

County Cowley

KANSAS



CASING:  
 8 5/8" 125' cem w/100 sx.

Elevation. 1252' DF

Production. Dry

Figures indicate Bottom of Formations.

|                        |      |
|------------------------|------|
| surface hole           | 40   |
| shale & lime shells    | 90   |
| lime & shale           | 125  |
| shale & lime shells    | 385  |
| shale & lime           | 555  |
| shale & lime shells    | 860  |
| shale                  | 1165 |
| sdv shale & lime strks | 1365 |
| sdv shale & lime shls  | 1501 |
| sdv shale & lime strks | 1740 |
| shale & lime strks     | 1880 |
| shale & lime           | 2075 |
| mdy shale & lime       | 2170 |
| shale & lime           | 2410 |
| sand & shale           | 2480 |
| lime & shale           | 2505 |
| lime & shale strks     | 2585 |
| shale & lime           | 2685 |
| Big Lime               | 2720 |
| sand                   | 2737 |
| shale - lime           | 2790 |
| lime & shale           | 2825 |
| lime                   | 2945 |
| shale                  | 3030 |
| shale & lime strks     | 3150 |
| shale                  | 3202 |
| chert & lime           | 3222 |
| lime                   | 3267 |
| lime & cherty strks    | 3280 |
| lime                   | 3611 |
| lime & shale           | 3625 |
| lime                   | 3635 |
| shale                  | 3665 |
| lime - Arbuckle        | 3713 |
| Total Depth            |      |

**TOPS: SCOUT**

|                          |      |
|--------------------------|------|
| Iatan Lime               | 1854 |
| Stalnaker Sand           | 1920 |
| Perry Gas Sand           | 2103 |
| Layton Sand              | 2387 |
| Checkerboard Lime        | 2687 |
| Cleveland Sand           | 2724 |
| Oswego                   | 2794 |
| Cherokee Shale           | 2950 |
| Mississippi Conglomerate | 3194 |
| Mississippi Chat         | 3202 |
| Mississippi Lime         | 3224 |
| Chattanooga Shale        | 3640 |
| Arbuckle Dolomite        | 3666 |