

NATIONAL ASSOCIATED PETROLEUM CO.

Office Memorandum

From Joe E. McGarrah

Date March 8, 1965

To Forrest H. Lindsay

Subject #1-A Dunn

SE NW NE Sect. 3-35S-5E  
Cowley County, Kansas

TYPE: Wildcat

STATUS: D & A

ELEVATIONS: D. F. 1238'; K. B. 1240'; ground 1236'.

TOTAL DEPTHS: 3158' driller; 3159' Schlumberger.

DATES: M. I. R. T. February 19, 1965. Dry and abandoned March 5, 1965.

CASING: 96' of 8 5/8" set at 100' with 75 sx cement, 3% C. C.

SPECIAL TESTS: Superior Testers; Schlumberger E. Log.

DESCRIPTION OF SPECIAL TESTS:

#1 DST: 3120-3158': Miss. formation. Open 1/2 hour. Shut in 20 minutes. Weak blow, died in 6 minutes, bypassed tool. Blow died 5 minutes. Rec. 75' mud. IFP 40#, FFP 78#, IBHP 318#, FBHP 144#.

FORMATION TOPS:	SAMPLES	E. LOGS
Layton zone	2340	2343
Layton sand	2408	2406
Cleveland sand zone	2652	2650
Oswego	2728	2726
Base Oswego	2862	2861
Miss.	3119	3120
Total depth	3158	3159

JEM:dc

Respectfully submitted,

*Joe E. McGarrah*  
Joe E. McGarrah

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Nat. Associated Petros. Co.

Complete Address: 502. Ritz Bldg. Tulsa Okla.

Lease Name N.C. Dunn "A" Well No. 1

Location SE - NW - SNE Sec. 3 Twp. 35 Rge. 5 (E) (W)

County Cowley Total Depth 3158

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Thoroughbred Drilling Co.

Address: Ritz Bldg. Tulsa Okla. License No. \_\_\_\_\_

Operation Completed: Hour 7:30 Day 4 Month 3 Year 1965

The Above well was plugged as follows:

Mudded hole to 180 -ft. with 40 lbs.  
mud - set a dry hole plug - added  $\frac{1}{2}$   
sax hulls and 25 sacks cement.  
Mudded hole from this point to 30 ft.  
set a plug - added  $\frac{1}{2}$  sax hulls and 8  
sacks cement. Capped Rat Hole with  
2 sacks cement.

(96' of 8" surface pipe cemented with 75 sacks)

I hereby certify that the above well was plugged as herein stated.

Charles Lane

Signed: Paul Tarpin  
Well Plugging Supervisor

*Thoroughbred*  **drilling company • tulsa**

517 RITZ BUILDING TELEPHONE LU 2-1181

March 8, 1965

Operator: National Associated Petroleum Co.  
Fifth Floor Ritz Bldg.  
Tulsa

Farm: Dunn 1-A  
Location: SE NW NE 3-35S-5E  
Cowley County, Kansas

MIRT 2-19-65  
COMP 3-4-65 D&A  
Surface Csg. 96 feet overall new 8 5/8"  
set @ 100' with 75 sax cut plus 300 c c  
9:00 P.M. 2-21-65

( )

0'	-	213'	Lime
213'	-	398'	Lime & shale streaks
398'	-	550'	Lime
550'	-	840'	Shale
840'	-	920'	Shale & Lime
920'	-	1020'	Shale
1020'	-	2044'	Lime & Shale
2044'	-	2196'	Shale & Hard Sand
2196'	-	2446'	Lime & Shale w/ hard sand
2446'	-	2532'	Sand & Shaley Lime
2532'	-	2698'	Lime & Shale
2698'	-	2762'	Sand & Lime
2762'	-	2872'	Lime
2872'	-	2888'	Lime & Shale
2888'	-	3128'	Shale & Lime streaks
3128'	-	3158'	Mississippi Chat & Lime

TD

THOROUGHBRED DRILLING CO.  
Daniel W. Brown