




Released
DRILLING COMPANY, INC.



3-3-14E8

114 WEST LOCUST — P.O. BOX 645 — EL DORADO, KANSAS 67042

March 27, 1985

CONFIDENTIAL

To: Teichgraeber Oil Operations
 P.O. Box 471
 El Dorado, Kansas 67042

Lease: Liertz #2

Location: Sec. 3, Twp. 3, Rge. 14E
 Nemaha County

Drilling Dates: *SW NWSE*
 March 11 thru March 23, 1985

AUG 11 1986
 KANSAS PROFESSIONAL SURVEYORS
 WICHITA BRANCH

Drilling Log

Surface T.D. 263'
 Surface Set 253' of 8 5/8" Surface Casing
 Cemented by Consolidated

263 - 430'	Shale
430 - 1233'	Shale w/Lime Streaks
1233 - 1520'	Lansing
1520 - 1563'	Kansas City
1563 - 2449'	Lime & Shale Mixed
2449 - 2627'	Mississippi
2627 - 2856'	Kinderhook
2856 - 3472'	Hunton
3472 - 3549'	Maquoketa
3549 - 3705'	Viola
3705 - 3840'	Simpson
3840 - 3870'	Arbuckle
3870'	T.D.

RECEIVED
 STATE CORPORATION COMMISSION

MAY 14 1985

CONSERVATION DIVISION
 Wichita, Kansas

TUBING RECORD size 2 7/8 set at 3530' packer at		Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No			
Date of First Production 04-23-85	Producing method <input type="checkbox"/> flowing <input checked="" type="checkbox"/> pumping <input type="checkbox"/> gas lift <input type="checkbox"/> Other (explain)				
Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio	Gravity
	75 Bbls	N/A MCF	15 Bbls	CFPB	