


10-3-145

EDCO DRILLING COMPANY, INC.



~~XXXX WESTWOOD ST~~ — P.O. BOX 645 — EL DORADO, KANSAS 67042

November 30, 1986

To: Teichgraeber Oil and Brown Energy Corporation
P. O. Box 471
El Dorado, KS 67042

Lease: Wenger "A" #1

Location: Sec. 10, Twp. 3, Rge. 14E
Nemaha County, Kansas

Drilling Dates: November 17, 1986 through November 27, 1986

Drilling Log:

Surface TD: 264 ft
Surface Set: 250 ft of 8 5/8" surface casing
Cemented By: Sun Cementing w/180 sacks Regular 3% CC/Ticket #1625

0 - 264	Surface hole
264 - 1289	Shale w/lime streaks
1289 - 1327	Lansing
1327 - 1497	Lansing - Kansas City
1497 - 1622	Kansas City
1622 - 2107	Shale w/lime streaks
2107 - 2380	Cherokee
2380 - 2534	Shale
2534 - 2682	Mississippi
2682 - 2925	Kinderhook
2925 - 3553	Hunton
3553 - 3597	Maquoketa
3597 - 3751	Viola
3751 - 3890	Simpson
3890	TD

METHOD OF COMPLETION

Production Interval

Disposition of gas: Vented
 Sold
 Used on Lease

Open Hole Perforation
 Other (Specify)

Dually Completed
 Commingled

3818' - 3826'
.....
2933' - 2943'
.....