


Company - CARTER OIL CO.
 Farm - Drancy Heirs No. 1

SEC. 13 T. 3 R. 11E
 SE SE SE

13-3-14E

Total Depth. 3152
 Comm. 2-28-49 Comp. 3-18-49
 Shot or Treated.
 Contractor. Earl F. Wakefield
 Issued. 7-23-49

County. Nemaha
 KANSAS



Elevation. 1274 LS

Production. Dry

CASING:

10 3/4" 138'
 13 3/4" 138'
 cem w/179 sx.

Figures Indicate Bottom of Formations.

. clay	20
. clay & lime & shells	50
. surface bowlers	85
. lime	220
. lime & shale	435
" pyrite strks.	
. shale sdy	648
. sand & shale	807
. lime & shale	1010
. sand shale	1060
. sand	1120
. lime	1172
. shale & lime strks	1230
. shale & sand strks	1308
. lime	1380
. lime & shale brks	1450
. lime	1526
. lime & shale	1565
. lime & shale brks	1615
. lime - shale strks	1661
. shale & lime strks	1815
. shale	1863
. sand & shale strks	1925
. sand & shale	2025
. shale sdy & lime strks	2075
. sand & shale lime strks	2128
. sand & shale	2210
. shale sdy & lime strks	2275
. shale lime strks	2330
. shale	2375
. shale & sand	2410
. shale	2604
. shale & sand	2640
. lime	2799
. shale	3077
. lime	3152
Total Depth	

Geological Tops:

. Howard	806
. Topeka	836
. K.C. line	1308
. Miss. Lime	2637
. Kinderhook Shale	2800
. Hunton Lime	3078
. Cherokee	1949

shows of oil, gas, & wtr.