

DONIPHAN OIL AND GAS CO.
C.N. Albers No. 1.

SEC. 14 T. 3 R. 19E.
SEc SW

Total Depth. 1725
Comm. 11-28-19
Shot or Treated.
Contractor.
Issued.

Comp. 4- 1920

County Doniphan



CASING.

15 1/2" 20' 8 1/2" 933'
12 1/2" 393' 65/8" 1635'
10" 685'

Elevation. 880'

Production. DRY.

Figures Indicate Bottom of Formations.

| | | | | | |
|----------------------------|-----|-------------------------|------|---------------------|------|
| soil | 5 | lime light | 735 | lime grey | 1580 |
| gravel | 15 | shale blk | 745 | shale light | 1596 |
| shale | 25 | lime light | 760 | lime grey | 1605 |
| lime grey | 30 | shale slatey dark | 765 | shale light sandy | |
| shale blue | 40 | lime grey | 790 | rotten | 1635 |
| lime grey | 45 | coal | 793 | lime white mass | 1673 |
| shale white | 55 | shale white | 873 | sandstone grey wtr | 1700 |
| lime white | 70 | lime white | 875 | lime broken | 1705 |
| shale dark | 75 | shale yellow | 905 | lime sand broken | 1715 |
| lime grey | 80 | lime light | 920 | lime broken pinkish | 1725 |
| shale white | 85 | shale blue | 928 | | |
| sdv shale white | 125 | shale light | 932 | Total Depth. | |
| shale dark | 165 | lime grey | 936 | | |
| lime | 180 | shale blue | 945 | | |
| shale light | 185 | shale blk seams of | | | |
| lime light | 200 | coal | 960 | | |
| shale light | 225 | shale light | 965 | | |
| lime light | 230 | lime grey | 975 | | |
| shale light | 235 | shale light | 995 | | |
| lime light | 238 | lime light | 998 | | |
| shale light | 240 | shale dark | 1005 | | |
| sand & BW trace gas | 255 | shale light | 1030 | | |
| shale white | 260 | lime | 1035 | | |
| lime grey | 285 | coal | 1038 | | |
| shale light | 290 | shale | 1070 | | |
| shale dark | 295 | lime | 1075 | | |
| sdv shale light | 300 | shale | 1085 | | |
| shale light | 309 | sdv shale | 1107 | | |
| shale red | 316 | lime | 1110 | | |
| shale light | 475 | shale | 1135 | | |
| shale dark | 480 | shale sdv | 1150 | | |
| shale light | 490 | shale blue | 1200 | | |
| lime grey | 495 | shale blue seams of | | | |
| shale light | 500 | coal | 1205 | | |
| lime white | 515 | shale light | 1245 | | |
| shale light | 520 | sand | 1275 | | |
| shale dark | 530 | shale dark | 1305 | | |
| lime light | 555 | sand light soft | 1325 | | |
| sdv shale light | 565 | salt water 150' of top. | | | |
| shale light | 580 | sand white | 1385 | | |
| lime light | 585 | shale light | 1395 | | |
| shale light | 595 | sand white water | 1420 | | |
| shale blue | 615 | shale blk blue | 1485 | | |
| lime grey | 630 | coal | 1492 | | |
| shale light | 655 | sdv shale | 1495 | | |
| shale sdv | 670 | coal | 1500 | | |
| shale dark | 690 | shale light | 1510 | | |
| shale light | 690 | broken lime | 1515 | | |
| shale dark | 695 | shale blue | 1530 | | |
| shale light chalky pinkish | 700 | sand red mod | 1575 | | |

Lausung-K.C.
P.S. = 730+