

SIDE ONE

18-4-14E State Geological Survey
AFFIDAVIT OF COMPLETION FORM WICHITA, BRANCH (REV) AGO-1

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: (Oil), Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

X Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Petro-Lewis Corporation

API NO. 15-131-20022

ADDRESS 5400 North Independence

COUNTY Nemaha

Oklahoma City, Oklahoma 73112

FIELD Wildcat

**CONTACT PERSON Randall Arnold

PROD. FORMATION Viola

PHONE (405) 949-9412

LEASE McClain

PURCHASER Cities Service Company

ADDRESS 1600 Broadway

WELL NO. #1

Denver, CO 80202

WELL LOCATION

DRILLING Silverado Drilling, Inc.

1980 Ft. from North Line and

CONTRACTOR

660 Ft. from East Line of

ADDRESS 435 Page Court

Wichita, KS 67202

the NE/4SEC. 18 TWP. 4S RGE. 14E

RECEIVED

STATE CORPORATION COMMISSION

WELL PLAT

PLUGGING N/A


APR - 5 1982

CONTRACTOR

ADDRESS

CONSERVATION DIVISION
Wichita, Kansas

KCC
KGS
(Office Use)



TOTAL DEPTH 3790 PBTD 3736

SPUD DATE 12-3-81 DATE COMPLETED 3-16-81

ELEV: GR 1284 DF KB 1288

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 261 DV Tool Used? No

AFFIDAVIT

STATE OF Oklahoma, COUNTY OF Oklahoma SS, I,

Randall Arnold OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS District Engineer (FOR)(OF) Petro-Lewis Corporation

OPERATOR OF THE McClain LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. #1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 16 DAY OF March, 1992, AND THAT

SIDE TWO

WELL LOG

18-4-14E

Show formation zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
Viola (DST) Recovered 2720' oil		3428	3501	Viola	3489'-93

Date of first production 3-16-82		Producing method (flowing, pumping, gas lift, etc.) Pumping		Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil 65 bbls.	Gas None MCF	Water .6 % bbls.	Gas-oil ratio N/A	CFPB
Disposition of gas (vented, used on lease or sold) N/A			Perforations		

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)							
Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20	261	Class H	250	2% CaCl
Production	7 7/8"	5.5	15.5	3770	Class A	50	
					RFC	150	2% cello flakes

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4spf	csg. gun	3489'-93

TUBING RECORD		
Size	Setting depth	Packer set at
2 1/16	3450'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD



DRILLER'S LOG

18-4-14E

81

SEP

COMPANY: Pendleton Land & Exploration, Inc.

SEC. 18 T. 4S R. 14E

WELL NAME: McClain #1

LOC. 25' E of C E/2 NE NE

RIG NO. #10

State Geological Survey
WICHITA, BRANCH

COUNTY: Nemaha

TOTAL DEPTH 3800'

ELEVATION

COMMENCED: 12-3-81

COMPLETED: 12-23-81

CONTRACTOR: Silverado Drilling, Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 261' w/250 sx. common, 2% cc.

PRODUCTION: 4 1/2" @ 3789' w/50 sx. Class A and 150 sx. RSC, 500 gal. chem-wash

LOG

(Figures Indicate Bottom of Formations)

Sand	503
Sand & Shale	1313
Shale	1443
Sand	1805
Shale & Sand	2075
Sand & Shale	2205
Shale	2510
Lime & Shale	2596
Shale	2758
Shale & Lime	2899
Shale	3800
<u>ROTARY TOTAL DEPTH</u>	<u>3800</u>

RECEIVED
STATE OF KANSAS
JAN 27 1982
GEOLOGICAL SURVEY
WICHITA, KANSAS

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Joseph B. Brungardt, Jr., Acct. of Silverado Drilling, Inc.