


County Jackson  
 KANSAS

Total Depth. 3603  
 Comm. 1-27-52 Comp. 2-12-52  
 Shot or Treated.  
 Contractor. Claude Wentworth Drlg. Co.  
 Issued. 4-12-52



CASING:

8 5/8" 201' cem. w/150' sx

Elevation. 1198 DF

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	35
sand & shells	40
shale & shells	201
shale	620
sandy shale	685
sandy lime & shale	695
sandy lime	745
lime & shale	1345
shale & shells	1405
lime & shale	1490
lime	1590
lime & shale	2045
shale, sand & lime	2330
lime	2789
lime	2793
lime	2822
lime	3343
lime	3351
lime	3438
sand & lime	3565
lime	3603
Total Depth	

BEST COPY AVAILABLE

Tops:

Howard	683
Topeka	743
Lansing	1270
Miss	2415
Kinderhook	2573
Hurton	2783
Maquoketa	3274
Viola	3343
Simpson	3438
Abuckle	3565

Slight show oil with lgt  
 poor porosity 2789-93'  
 Slight show heavy oil, fair  
 to good porosity & good  
 saturation 3343-51'  
 Lost circ. at 3430' regained  
 same  
 Ran Schlumberger survey to 3603'

very slightly oil cut muc & 420'  
 of wtr. No BHP

DST: #1 2787-2822' tool open  
 1 hr. rec. 3' of oil, 130' of  
 oil cut mud & 210' of muddy  
 wtr. BHP 950'

DST: #2 3341'-3351' tool  
 open 1-1/2 hrs. rec. 70' of