

22-7-13 E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PHILLIPS PET. CO.
Farm- Hladky "A" No. 1

SEC. 22 T. 7 R. 13E
C NE NW
660' FNL, 660' FBL
NW74

Total Depth. 3370'
Comm. 12-5-64 Comp. 5-14-64
Shot or Treated.
Contractor. Jackman & Jackman
Issued. 12-26-64

County Jackson
KANSAS



CASING:

Elevation. 1195.66'

10 3/4" 219' w/150 sx cem.
7" 3357.61' w/81' sx cem.

Production Exp: 59 BOE/D & 62% wtr

Figures indicate Bottom of Formations.

clay, rock	15
shale	85
lime, shale	125
shale, lime	225
shale, lime shells	1035
lime	1045
shale, w/lime stks	1262
lime w/shale strks	1330
lime, shale	1570
lime	1611
shale, shells	1690
lime	1805
lime, shale	1860
shale, shells	2431
sand	2460
lime	2544
shale	2751
lime	3263
shale	3299
lime	3370
Total Depth	
PB	3228

1-3: Ran 2" Slim hole tubing
3286' to produce Viola.
Ran 2 7/8" Slim hole tubing set
@ 2734' to produce Hunton.

BEST COPY
AVAILABLE

TOPS: SCOUT	
* Topeka	740
* Heebner	1048
* Lansing Kansas City	1262
* Drum	1453
* B/Kansas City	1611
* Cherokee	1815
Burgess sand	2430
Mississippi	2461
Kinderhook	2540
Hunton	2751
Maquoketa	3235
Viola	3297

Perf: Hunton 2753-2760'
Perf: Viola 3297-3308'