

19-7-17E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRED B. ANSCHUTZ
Farm- Worner No. 1

SEC. 19 T. 7 R. 17E
C NE SE

Total Depth. 2992'
Comm. 5-1-64 Comp. 5-10-64
Shot or Treated.
Contractor. Fred B. Anschutz
Issued. 7-11-64

County Atchison
KANSAS



CASINO:

Elevation. 1027' KB

8 5/8" 111.5' cem w/ 100 sx
5" 2462' cem w/ 50 sx

Production. 52 BOPD PLUS 82% WTR

Figures Indicate Bottom of Formations.

surface	27
shale & shells	111
shale & lime	355
shale	821
shale & lime	1377
shale	1970
Dolomite	2013
lime, chert	2072
lime & shale	2283
Kinderhook	2376
lime	2632
lime Dolomite	2728
lime, chert, Dolomite	2820
lime	2866
Arbuckle	2992 RTD
Total Depth	

TOPS: SCOUT	
Lansing (Smp)	743
Base Kansas City (Smp)	1079
Mississippi	1965
Kinderhook	2191
Hunton	2373
Viola	2745
Simpson shale	2869
Simpson Dolomite	2877
Simpson sand	2898
Arbuckle	2958

oil (miser?)

1079
1027
-52