


EDCO DRILLING COMPANY, INC.



2-7-18E

~~XXXXXXXXXXXX~~ — P.O. BOX 645 — EL DORADO. KANSAS 67042
December 15, 1986

To: Theodore I. Leben
105 South Broadway, Suite 640
Wichita, KS 67202

Lease: Childress #2

Location: Sec. 2, Twp. 7 S, Rge. 18E
Atchison County, Kansas

Drilling Dates: November 25, 1986 through December 5, 1986

Drilling Log:

Surface TD: 180'
Surface Set: 168.95 ft of 8 5/8" surface casing
Cemented by: Sun Cementing w/80 sacks of 60-40 pos

0 - 180	Surface hole
180 - 643	Shale w/lime streaks
643 - 756	Lansing
756 - 959	Lime
959 - 1078	Shale & Sand
1078 - 1362	Shale & lime
1362 - 1793	Shale & sand
1793 - 1840	Mississippi
1840	TD

STATE COMMISSION

JAN 14 1987

CONSERVATION DIVISION
Wichita, Kansas

Confidential

2-7-18E

Attachment ACO-1

Re: Childress #2-2
C N/2 SW Sec. 2-7S-18E
Atchison County, Kansas

DST #2 Continued --	Gauged	1,420,000 in 10 min.
		1,694,000 in 20 min.
		1,950,000 in 30 min.
		2,075,000 in 40 min.
		2,075,000 in 60 min.

No recovery.

ISIP taken during initial flow period
when tool did not open 650#

FSIP	650	IFP not taken
		FFP 465-545

HP 880 - 745	Temp 96°
--------------	----------