

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG


State Geological Survey WICHITA BRANCH

S. 27 T. 7S R. 19 E

Loc. SE NW SW

County Jefferson

640 Acres



Locate well correctly

Elev.: Gr. 1096

DF KB 1100

API No. 15 — 087 — 20,045
County Number

Operator

Olympic Petroleum Company

Address

Tulsa, Oklahoma 74114

Well No.

1

Lease Name

James Schrick

Footage Location

C SE NW SW Section 27

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Jackman & Jackman

Geologist

James E. Gribi

Spud Date

10-20-81

Date Completed

10-29-81

Total Depth

2,750

P.B.T.D.

None

Directional Deviation

Oil and/or Gas Purchaser

None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2	8 5/8		286	Regular	225	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
None					
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval (s)	
				None	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Olympic Petroleum Company DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry hole

Well No. 1 Lease Name James Schrick

S 27 T 7S R 19 E SE NW SW Section 27

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Ran Petro-Log Induction and Compensated Density Logs.				
<u>Electric Log Tops</u>				
Heebner Sh.	330 (+ 770)	Hunton Lm	2150	(-1050)
Lansing Lm.	594 (+ 508)	Maquketa Sh.	2368	(-1268)
Kansas City Lm.	754 (+ 346)	Viola Lm.	2436	(-1336)
Base Kansas City	923 (+ 177)	Simpson	2600	(-1500)
Cherokee	1150 (- 50)	Arbuckle Lm.	2695	(-1595)
McLouth Sand	1656 (- 556)	Rotary Total Depth	2750	(-1650)
Mississippian Lm.	1731 (- 631)	Electric Log T. D.	2750	(-1650)
Kinderhook Sh.	2064 (- 964)			
<u>Drill Stem Tests</u>				
DST No. 1-1667 to 1688. Open 15 mins. with strong blow. Shut in 30 mins. Open 60 mins. with good blow which gradually decreased. Shut in 90 mins. Recovered 1310 feet of saltwater with rainbow show of oil, no show of gas.				
IFP 305 - 540 ISIP 570/30 mins.				
FFP 560 - 570 FSIP 570/90 mins.				
MUD: Wght. 8.9, Vis 40, Wtr. Ls. 11				
DST No. 2-2063-2158. Open 30 mins. with weak blow. Shut in 60 mins. Open 20 mins. with no blow. Shut in 40 mins. Recovered 3 feet of mud with oil specks.				
IFP 40 - 40 ISIP 290/60 mins.				
FFP 40 - 40 FSIP 105/40 mins.				
DST No. 3-2611-2631. Open 15 mins. with good blow. Shut in 30 mins. Open 60 mins. with good blow throughout. Shut in 90 mins. Recovered 1700 feet of saltwater with no show of oil.				
IFP 115 - 395 ISIP 950/30 mins.				
FFP 405 - 825 FSIP 950/90 mins.				
Before test mud checked: Wght. 9.0, Vis. 45, Wtr. Ls. 12.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Olympic Petroleum Company
	<i>James E. Silver</i> Signature
	James E. Silver, Managing Partner Title
	November 11, 1981 Date

11-1-135